

SUMMARY OF QUANTITIES					% FEDERAL % STATE CONSTRUCTION AND SAFETY TYPE CODE			
CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	0004 ROADWAY	0011 STRUCTURE		
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	*	EACH	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE		CAL DA	10	10			
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	*	EACH	1	1			
70300100	SHORT-TERM PAVEMENT MARKING		FOOT	160	160			
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"		FOOT	4610	4610			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SO FT	2041	2041			
70400100	TEMPORARY CONCRETE BARRIER		FOOT	481.3	481.3			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER		FOOT	481.3	481.3			
* 78001120	PAINT PAVEMENT MARKING - LINE 5"		FOOT	2305	2305			
* 78200410	GUARDRAIL MARKERS, TYPE A	*	EACH	16	16			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	*	EACH	3	3			
78300100	PAVEMENT MARKING REMOVAL		SO FT	582	582			
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	*	CU YD	111		111		
X4811300	AGGREGATE SHOULDERS, TYPE B (SPECIAL)	*	TON	57	57			
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	*	EACH	1		1		
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	*	EACH	1		1		
X5080600	MECHANICAL SPLICERS	*	EACH	48		48		
X7200201	WIDTH RESTRICTION SIGNING	*	L SUM	1	1			
Z0001900	ASBESTOS BEARING PAD REMOVAL	*	EACH	44		44		
Z0013798	CONSTRUCTION LAYOUT	*	L SUM	1	1			
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	*	EACH	2	2			
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	*	EACH	2	2			
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	*	SO FT	831		831		

\*Specialty Items

FILE NAME =	USER NAME = laughtinr1	DESIGNED -	REVISED -
c:\pwork\pwork\laughtinr1\d0231868\0672853-sht-500.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / in.	CHECKED -	REVISED -
	PLOT DATE = Aug-11-2010 03:44:20PM	DATE -	REVISED -

<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>		<b>SUMMARY OF QUANTITIES</b>			
SCALE: NONE	SHEET NO. 30F	3SHEETS	STA.	TO STA.	
F.A.P. RTE. 608	SECTION 122B-2	COUNTY MACOUPIN	TOTAL SHEETS 53	SHEET NO. 5	CONTRACT NO. 72B53
FED. ROAD DIST. NO. 6		ILLINOIS FED. AID PROJECT			