

PAVEMENT MARKING SCHEDULE							
LOCATION	PREFORMED PLASTIC PAVEMENT MARKING TYPE B-INLAID-5"	URETHANE PAVEMENT MARKING-LINE 5"	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING TAPE, TY. III 8" (STAGE I)
	FOOT	FOOT	SO FT	EACH	EACH	SO FT	FOOT
CL. STA 682+50 TO 690+50.0	90	110	101				
RT. STA 680+78.0 TO 690+50.0		972					
LT. STA 680+78.0 TO 690+50.0		972					
CL. STA 682+50.0 TO 684+25.59				6	6		
CL. STA 688+32.59 TO 690+50.0				4	4		
STAGE I							
LT. STA 661+00.0 TO 684+54.41 (YELLOW)						981	
LT. STA 688+02.59 TO 689+25.0 (YELLOW)						51	
RT. STA 661+00.0 TO 671+73.03 (WHITE)						447	
RT. STA 674+61.14 TO 689+19.95 (WHITE)						608	
STA 674+61.14 TO 676+34.35 (YELLOW) (ALONG LEFT EDGE OF EXIT RAMP)						72	
STA 671+73.03 TO 676+26.80 (WHITE) (ALONG RIGHT EDGE OF EXIT RAMP)						189	
STAGE II							
LT. STA 661+00.0 TO 688+55.5 (YELLOW)						1,148	
RT. STA 661+00.0 TO 672+56.51 (WHITE)						482	
RT. STA 676+35.67 TO 690+00.0 (WHITE)						568	
LT. 684+47.69 TO 688+57.76 (YELLOW)							615
RT. STA 680+78.0 TO 690+50.0			405				
LT. STA 680+78.0 TO 690+50.0			405				
TOTAL	90	2054	911	10	10	4,548	615

SCHEDULE OF BR. APP. PAVEMENT CONNECTOR	
LOCATION	BRIDGE APP. PAVEMENT CONNECTOR (PCC) SQ YD
STA 683+74.41 TO 684+24.41	200
STA 688+32.59 TO 688+82.59	200
TOTAL	400

SCHEDULE OF PAVEMENT REMOVAL			
LOCATION	PAVEMENT REMOVAL	APPROACH SLAB REMOVAL	PAVED SH. REMOVAL
	SO YD	SO YD	SO YD
STA 683+75.41 TO 684+24.41	186		
STA 688+32.59 TO 688+82.59	207		
STA 684+24.41 TO 684+54.41		114	
STA 688+02.59 TO 688+32.59		114	
LT. STA 680+78.0 TO 684+58.58			193
RT. STA 680+78.0 TO 684+02.29			245
LT. STA 688+57.76 TO 690+50.0			111
RT. STA 687+98.74 TO 690+50.0			238
TOTAL	393	228	787

PROPOSED SCHEDULE OF STEEL PLATE BEAM GUARDRAIL							
LOCATION	SPBGR, TY A, 6' POST	SPBGR, TY A, 9' POST	TYPE 6 TERMINAL	TYPE 1 TERMINAL, SPECIAL (TANGENT)	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER-DIRECT APPLIED	GUARDRAIL REMOVAL
	FOOT	FOOT	EACH	EACH	EACH	EACH	FOOT
RT. STA 680+33.35 TO 683+78.35	345						
LT. STA 680+58.05 TO 684+44.05		386					
LT. STA 684+44.05 TO 684+75.3			1				
RT. STA 683+78.35 TO 684+09.6			1				
LT. STA 680+08.43 TO 680+58.05				1		1	
RT. STA 679+83.11 TO 680+33.35				1		1	
RT. STA 679+83.24 TO 683+25.19							342
LT. STA 680+07.96 TO 683+25.19							317
RT. STA 683+25.19 TO 684+46.92							122
LT. STA 683+25.19 TO 685+10.22							185
RT. STA 679+83.11 TO 688+02.59					7		
LT. STA 680+08.43 TO 688+02.59					7		
TOTAL	345	386	2	2	14	2	966

PIPE CULVERT REMOVAL SCHEDULE	
LOCATION	FOOT
LT. STA 688+83.52	64
TOTAL	64

SCHEDULE OF TEMP. CONC. BARRIER	
LOCATION	FOOT
STA 680+78.0 TO 688+55.5	778
TOTAL	778

TREE REMOVAL SCHEDULE	
LOCATION	UNITS
RT. STA 683+72 42' OFFSET	18
TOTAL	18