

SUMMARY OF QUANTITIES

URBAN 90% FED / 10% STATE

CODE NUMBER	PAY ITEM	UNIT	QUANTITY	ROADWAY 0005	STRUCTURES 0014
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18	18	
20200100	EARTH EXCAVATION	CU YD	550	550	
20400800	FURNISHED EXCAVATION	CU YD	110	110	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	370		370
25000200	SEEDING, CLASS 2	ACRE	2.6	2.6	
25000350	SEEDING, CLASS 7	ACRE	2.6	2.6	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	172	172	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	172	172	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	172	172	
25100115	MULCH, METHOD 2	ACRE	5.2	5.2	
25100630	EROSION CONTROL BLANKET	SQ YD	9171	9171	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	500	500	
28000400	PERIMETER EROSION BARRIER	FOOT	2116	2116	
28100107	STONE DUMPED RIPRAP, CLASS A4	SQ YD	293	293	
28200200	FILTER FABRIC	SQ YD	293	293	
35600724	HOT - MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	654	654	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.4	0.4	
40600300	AGGREGATE (PRIME COAT)	TON	2.0	2.0	
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	450	450	
40600990	TEMPORARY RAMP	SQ YD	38	38	
40603245	POLYMERIZED HOT - MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	98	98	
40603310	HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	111	111	
40603575	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	65	65	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	400	400	
44000100	PAVEMENT REMOVAL	SQ YD	393	393	
44004250	PAVED SHOULDER REMOVAL	SQ YD	787	787	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	89	89	
50102400	CONCRETE REMOVAL	CU YD	71.5		71.5
50104650	SLOPE WALL REMOVAL	SQ YD	840		840
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1

SUMMARY OF QUANTITIES

90% FED / 10% STATE

URBAN

CODE NUMBER	PAY ITEM	UNIT	QUANTITY	ROADWAY 0005	STRUCTURES 0014
50105220	PIPE CULVERT REMOVAL	FOOT	64	64	
50157300	PROTECTIVE SHIELD	SO YD	680		680
50200100	STRUCTURE EXCAVATION	CU YD	677		677
50300225	CONCRETE STRUCTURES	CU YD	196.9		196.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	574.1		574.1
50300260	BRIDGE DECK GROOVING	SO YD	1449		1449
50300300	PROTECTIVE COAT	SO YD	1869		1869
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	20,750		20,750
50500505	STUD SHEAR CONNECTORS	EACH	4,374		4,374
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	159,240		159,240
50800515	BAR SPLICERS	EACH	1,433		1,433
51100100	SLOPE WALL 4 INCH	SO YD	742		742
51500100	NAME PLATES	EACH	1		1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	79		79
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12		12
52100520	ANCHOR BOLTS, 1"	EACH	36		36
52100530	ANCHOR BOLTS, 1 1/4"	EACH	12		12
52100540	ANCHOR BOLTS, 1 1/2"	EACH	12		12
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	14	14	
58700300	CONCRETE SEALER	SO FT	2,398		2,398
59000200	EPOXY CRACK INJECTION	FOOT	68		68
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	185		185
60100945	PIPE DRAINS 12"	FOOT	326	326	
20046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	190		190
60240225	INLETS, TYPE B, TYPE 4 FRAME AND GRATE	EACH	1	1	
60500060	REMOVING INLETS	EACH	1	1	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	345	345	
* 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	386	386	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	

*Specialty Items

FILE NAME *	USER NAME *	DESIGNED LLO	REVISED -
ca\pwwork\pwwork\laughlin\08231206\06	2A64-shl-S00.dgn	DRAWN JJS	REVISED -
	PLOT SCALE * 100.0000' / in.	CHECKED MTM	REVISED -
	PLOT DATE * Aug-11-2010 01:02:38PM	DATE JANUARY 2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-72 SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-3HB-5)BR	SANGAMON	84	3
S.N. 084-007B		CONTRACT NO. 72C70		
FED. ROAD DIST. NO. 6		ILLINOIS FED. AID PROJECT		