

URBAN
90% FED./10% STATE

SUMMARY OF QUANTITIES					
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	ROADWAY 0005	STRUCTURES 0014
63200310	GUARDRAIL REMOVAL	FOOT	966	966	
66700095	PERMANENT SURVEY MARKERS	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1	1	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	615	615	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4,548	4,548	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	778	778	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	778	778	
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID ^{LINE} 5"	FOOT	90	90	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	14	14	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
78300100	PAVEMENT MARKING REMOVAL	SO FT	911	911	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10	10	
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA, GALVANIZED STEEL	FOOT	180		180
Z0001904	STRUCTURAL STEEL REMOVAL	L SUM	1		1
Z0003802	REMOVAL OF EXISTING BEARINGS	EACH	24		24
Z0004552	APPROACH SLAB REMOVAL	SO YD	228	228	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	9		9
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	24		24
Z0018004	DRAINAGE SCUPPERS, DS-12	EACH	4		4
Z0026346	NIGHT TIME WORK ZONE LIGHTING	L SUM	1		1
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1	

URBAN
90% FED./10% STATE

SUMMARY OF QUANTITIES					
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	ROADWAY 0005	STRUCTURES 0014
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1	
Z0032300	JACKING EXISTING SUPERSTRUCTURE	L SUM	1		1
Z0034806	MODULAR EXPANSION JOINT - SWIVEL 6"	FOOT	77		77
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SO FT	500		500
X0325642	HIGH LOAD MULTI-ROTATION ^{CAL} BEARINGS, GUIDED EXPANSION, 300K	EACH	6		6
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	507		507
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1		1
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	2,054	2,054	
Z0016702	DETOUR SIGNING	L SUM	1		1

* SPECIALTY ITEMS

Rev.

FILE NAME :	USER NAME :	DESIGNED LLO	REVISED -
ca:\pwork\pwork\laughlin\108231286\062964-shit-500.dgn	laughlin1	JJS	REVISED -
	PLOT SCALE :	CHECKED MTM	REVISED -
	100,0000 / in.	DATE JANUARY 2010	REVISED -
	PLOT DATE :		
	Aug-11-2010 01:02:38PM		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-72 SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-3HB-5)BR	SANGAMON	84	4
S.N. 084-0078			CONTRACT NO. 72C70	
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				