

Station Range			Width	Length	Area	SURFACE REMOVAL	LEVEL BINDER	CAPE SEAL	AGG. SHLDR	BIT MAT'L PRIME COAT	AGG. PRIME COAT	SHORT TERM PAVTMKG	WORK ZONE PAVTMKG	TEMP. RAISED PAVT.MKR	HMA SURF. REM. BUTT JT	TEMP RAMP
			(FT)	(FT)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(FT)	(Ton)	(EACH)	(FT)	(SQ FT)		(SQ YD)	(SQ YD)
670+00	TO	664+84	38	516	2,179	2,179	92	2,179	--	0.83	4	52	17	13	63	21
664+84	TO	638+00	18	2,684	5,368	5,368	225	5,368	153	2.04	11	268	89	67	--	--
638+00	TO	565+50	18	7,250	14,500	14,500	609	14,500	206	5.51	29	725	242	181	--	--
565+50	TO	503+00	18	6,250	12,500	12,500	525	12,500	356	4.75	25	625	208	156	--	--
503+00	TO	490+00	18	1,300	2,600	2,600	109	2,600	74	0.99	5	130	43	33	--	--
490+00	TO	376+50	18	11,350	22,700	22,700	953	22,700	646	8.63	45	1,135	378	284	--	--
376+50	TO	369+34	18	716	1,432	1,432	60	1,432	41	0.54	3	72	24	18	--	--
Station Eqn. 370+37.60 (BK) = 369+34.20 (AH)					--	--	--	--	--	--	--	--	--	--	--	--
370+38	TO	312+00	18	5,838	11,675	11,675	490	11,675	332	4.44	23	584	195	146	--	--
312+00	TO	238+50	18	7,350	14,700	14,700	617	14,700	419	5.59	29	735	245	184	--	--
238+50	TO	226+55	18	1,195	2,390	2,390	100	2,390	68	0.91	5	120	40	30	--	--
226+55	TO	222+09	18	446	892	892	37	892	13	0.34	2	45	15	11	--	--
222+09	TO	219+42	18	267	534	534	22	534	15	0.20	1	27	9	7	--	--
219+42	TO	209+63	18	979	1,958	1,958	82	1,958	28	0.74	4	98	33	24	--	--
209+63	TO	207+82	18	181	362	362	15	362	--	0.14	1	18	6	5	--	--
207+82	TO	202+08	18	574	1,148	1,148	48	1,148	--	0.44	2	57	19	14	--	--
202+08	TO	201+30	18	78	156	156	7	156	2	0.06	0.31	8	3	2	--	--
201+30	TO	196+16	18	515	1,029	1,029	43	1,029	29	0.39	2	51	17	13	30	10
Bridge Omission Sta. 196+15.50 to Sta. 195+90.50					--	--	--	--	--	--	--	--	--	--	--	--
195+91	TO	192+50	18	341	681	681	29	681	19	0.26	1	34	11	9	60	20
<b>Totals</b>			<b>47,828</b>	<b>96,803</b>	<b>96,803</b>	<b>4,066</b>	<b>96,803</b>	<b>2,402</b>	<b>37</b>	<b>194</b>	<b>4,783</b>	<b>1,594</b>	<b>1,196</b>	<b>153</b>	<b>51</b>	

PAINT PAVEMENT MARKING LINE 5"	
	Length (FT)
Edge Line	95,707
Skip Dash	10,050
One Way -No Pass	17,500
No Passing Zone	18,000
<b>TOTAL</b>	<b>123,257</b>

PAVEMENT PATCHING	
Type I	50
Type II	100
Type III	50