

STRIPING SCHEDULE

STATION TO STATION				TEMPORARY PAINT PAVEMENT MARKING LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 4"	PAVEMENT MARKING REMOVAL
				FT	SQ FT	FT	SQ FT
STAGE I:							
LT STA	3183+17	TO	LT STA 3188+51	534	178	534	178
RT STA	3181+83	TO	RT STA 3189+03	-	240	-	-
CENTERLINE:							
STA	3182+81	TO	STA 3188+55	144	-	144	48
STAGE II:							
LT STA	3181+95	TO	LT STA 3189+55	-	253	-	-
RT STA	3182+81	TO	RT STA 3188+87	606	202	606	202
STAGE CONSTRUCTION STOP BARS:							
TOTALS:				1284	921	1284	428

GUARDRAIL SCHEDULE

STATION TO STATION				STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE G	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	GUARDRAIL REMOVAL	GUARDRAIL MARKER, TYPE A	TERMINAL MARKER - DIRECT APPLIED
				FT	EACH	EACH	FT	EACH	EACH
LT STA	3182+91	TO	LT STA 3183+06	-	-	-	15	-	-
LT STA	3183+06	TO	LT STA 3183+56	-	-	1	50	1	1
LT STA	3183+56	TO	LT STA 3184+19	63	-	-	63	1	-
LT STA	3184+19	TO	LT STA 3184+64	-	1	-	42	-	-
BRIDGE OMISSION									
LT STA	3186+53	TO	LT STA 3186+86	-	-	-	33	-	-
LT STA	3186+86	TO	LT STA 3187+31	-	1	-	45	1	-
LT STA	3187+31	TO	LT STA 3188+81	150	-	-	150	1	-
LT STA	3188+81	TO	LT STA 3189+31	-	-	1	50	1	1
LT STA	3189+31	TO	LT STA 3189+47	-	-	-	16	-	-
BRIDGE OMISSION									
RT STA	3182+37	TO	RT STA 3182+87	-	-	1	-	-	1
RT STA	3182+87	TO	RT STA 3183+06	19	-	-	-	1	-
RT STA	3183+06	TO	RT STA 3184+37	131	-	-	131	2	-
RT STA	3184+37	TO	RT STA 3184+82	-	1	-	37	-	-
BRIDGE OMISSION									
RT STA	3186+68	TO	RT STA 3187+05	-	-	-	37	-	-
RT STA	3187+05	TO	RT STA 3187+50	-	1	-	45	1	-
RT STA	3187+50	TO	RT STA 3188+12	62	-	-	62	1	-
RT STA	3188+12	TO	RT STA 3188+62	-	-	1	50	-	1
RT STA	3188+62	TO	RT STA 3189+62	-	-	-	100	-	-
TOTALS:				425	4	4	926	10	4

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (WIDENING) (cut)	EARTH EXC (WIDENING) ADJ. FOR SHRINKAGE	CHANNEL EXCAVATION (cut)	CHANNEL EXCAVATION ADJ. FOR SHRINKAGE	STRUCTURE EXCAVATION (cut)	STRUCTURE EXCAVATION ADJ. FOR SHRINKAGE	EMBANKMENT (fill)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
STA 3181+66 TO 3182+00	16.61	12.46	0.00	0.00			0.05	12.41
STA 3182+00 TO 3183+00	48.85	36.63	0.00	0.00			3.12	33.51
STA 3183+00 TO 3184+00	48.85	36.63	0.00	0.00			4.55	32.08
STA 3184+00 TO 3184+54.8	26.77	20.08	0.00	0.00			0.18	19.90
BRIDGE OMISSION					442.00	331.50	0.00	331.50
N. ABUTMENT	0.00	0.00	1434.20	717.10			0.00	717.10
STA 3186+72 TO 3187+00	13.68	10.26	0.00	0.00			0.86	9.40
STA 3187+00 TO 3188+00	48.85	36.63	0.00	0.00			5.75	30.88
STA 3188+00 TO 3189+00	48.85	36.63	0.00	0.00			6.19	30.44
STA 3189+00 TO 3189+81	39.57	29.67	0.00	0.00			1.44	28.23
TOTAL =	292.0	219.0	1434.2	717.1	442.0	331.5	22.1	1245.5