

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 90% FED. / 10% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0014		
28100107	STONE RIPRAP, CLASS A4	SQ YD	164	164		
28200200	FILTER FABRIC	SQ YD	164	164		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	38	38		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	89	89		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	100	100		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	42	42		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	500	500		
45200300	JOINT OR CRACK FILLING	POUND	70	70		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	15	15		
50102400	CONCRETE REMOVAL	CU YD	60.7	60.7		
50300100	FLOOR DRAINS	EACH	4	4		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	57.6	57.6		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6930	6930		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	97	97		
52000216	FINGER PLATE EXPANSION JOINT, 5"	FOOT	132	132		
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	140.5	140.5		
58700300	CONCRETE SEALER	SQ FT	80151	80151		
66101150	HOT-MIX ASPHALT SHOULDER CURB	FOOT	100	100		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10		
67100100	MOBILIZATION	L SUM	1	1		
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	300	300		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	4209	4209		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3	3		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1503	1503		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3	3		
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	400	400		
X5080600	MECHANICAL SPLICERS	EACH	280	280		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	100	100		
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	100	100		
Z0018800	DRAINAGE SYSTEM	L SUM	1	1		
Z0073350	TEMPORARY SLAB SUPPORT SYSTEM	EACH	4	4		
Z0076000	TRAINEES	HOURL	500	500		

INDEX OF SHEETS

- 1 COVER SHEET
- 2 SUMMARY OF QUANTITIES, INDEX OF SHEETS, HIGHWAY
STANDARDS, GENERAL NOTES, & COMMITMENTS
- 3 TYPICAL SECTION
- 4 SCHEDULES OF QUANTITIES & DETAILS
- 5 PLAN & PROFILE SHEET
- 6-7 DETOUR SIGNING
- 8-23 STRUCTURE PLANS
- 24-43 EXISTING STRUCTURE PLANS FOR REFERENCE ONLY

HIGHWAY STANDARDS

000001-05	701451-01
001001-02	701901-01
001006	780001-02
701400-04	781001-03

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - * AMERENIP (GAS & ELECTRIC)
 - * CHARTER COMMUNICATIONS, INC. (CABLE TV)
 - * CITY OF COLUMBIA (WATER & SANITARY SEWER)
 - * VILLAGE OF DUPO (WATER & SANITARY SEWER)
 - * VILLAGE OF DUPO (GAS)
 - * HARRISONVILLE TELEPHONE CO. (COMMUNICATIONS)
 - * PRAIRIE DU PONT PUBLIC WATER (WATER)
 - * SUGAR LOAF TOWNSHIP SEWER SYSTEM (SANITARY SEWER)
- MEMBERS OF J.U.L.I.E. CALL TOLL FREE (800) 892-0123 OR 811 AND ARE INDICATED BY *.
NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. PAVEMENT MARKING REMOVAL SHALL BE BY WATER BLAST METHOD.
5. THE DETOUR SIGNING WILL BE PAID FOR UNDER CONTRACT #76882. THE SIGNS FOR THE CLOSURE OF THE BRIDGE OVER THE UPRR SHALL REMAIN UP FOR THE DURATION OF THAT PROJECT, COORDINATE WITH CONTRACT #76882.
6. ANY AREAS DISTURBED DUE TO CONSTRUCTION ACTIVITIES SHALL BE SEEDED (TEMPORARY AND PERMANENT) AT THE CONTRACTOR'S EXPENSE AND NO OTHER COMPENSATION WILL BE PERMITTED.
7. PROPOSED PAVEMENT MARKINGS SHALL COORDINATE WITH EXISTING PAVEMENT MARKINGS. "POLYUREA PAVEMENT MARKING - LINE 4 INCH" SHALL BE USED ON CONCRETE. "THERMOPLASTIC PAVEMENT MARKING - LINE 4 INCH" SHALL BE USED ON HMA.
8. THE COST TO GRADE, SMOOTH, OR OTHERWISE FILL WITH SOIL ALL IRREGULARITIES IN THE AREA TO BE COVERED WITH FILTER FABRIC SHALL BE INCLUDED IN THE COST OF "FILTER FABRIC".

COMMITMENTS

NONE

**Specialty Items*

FILE NAME = c:\pwork\pwork\owenb\vdms66748\87633-shr-plan.dgn	USER NAME = owenbj DESIGNED - DRAWN - CHECKED - PLOT DATE = 8/11/2010	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I RTE. 255	SECTION 82-7HB-I	COUNTY ST. CLAIR	TOTAL SHEETS 43	SHEET NO. 2
SCALE: NA SHEET NO. 1 OF 1 SHEETS STA. TO STA.				FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT CONTRACT NO. 76C33					