

EARTHWORK				
LOCATION	EARTH EXCAVATION (CUT)	FOR INFORMATION ONLY		
		ADJUSTED EARTH EXCAVATION (ADJ. CUT)	EMBANKMENT (FILL)	WASTE
	CY	CY	CY	CY
EARTHWORK FROM STA. 23+85 TO 228+44.92	43100	34480	3462	31018
TOTAL	43100	34480	3462	31018

NOTE: ADJUSTED EARTH EXCAVATION CALCULATED ASSUMING A 20% SHRINKAGE FACTOR. THE QUANTITY CALCULATED FOR WASTE IS BASED ON THE ADJUSTED EARTH EXCAVATION QUANTITY.

GRADING AND SHAPING DITCHES		
STATION	OFFSET	LENGTH (FT)
24+34	LT	41
41+00	LT	39
146+89.11	LT	47
153+44.00	LT	58
156+04.40	LT	70
162+39.59	LT	40
170+75 (Ditch along W. Side of Dean Rd.)	LT	105
186+71.90	RT	65
200+71	RT	50
206+73.11	RT	35
214+41.35	RT	55
217+16.61	RT	52
TOTAL		657

FILE NAME = miscellaneous.sheet.dgn	USER NAME = russellm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -		SCALE:	SHEET NO. 2 OF 13 SHEETS	STA.	TO STA.	317	15W-2,RS-3 16W-3,RS-5	FULTON	171	21
		CHECKED -	REVISED -							CONTRACT NO. 88098			
		DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								