

CLASS D PATCHES 12"									
PATCHING UNIT	SIZE (FT x FT)			TYPE II		TYPE III		TYPE IV	
				# OF PATCHES	SQ. YD.	# OF PATCHES	SQ. YD.	# OF PATCHES	SQ. YD.
EAST END OF PROJECT TO HAMM RD.	6	X	13	46	398.7				
	8	X	13	4	46.2				
	10	X	13	7	101.1				
	12	X	13			2	34.7		
	15	X	13			5	108.3		
	20	X	13					5	144.4
	40	X	13					4	231.1
	50	X	13					1	72.2
HAMM RD. TO OAK GROVE RD.	6	X	13	5	43.3				
	8	X	13	2	23.1				
	10	X	13	1	14.4				
	12	X	13			1	17.3		
	20	X	13					4	115.6
	4	X	20	2	17.8				
	4	X	50			7	155.6		
OAK GROVE RD. TO DEAN RD.	6	X	13	108	936.0				
	8	X	13	7	80.9				
	10	X	13	6	86.7				
	12	X	13			1	17.3		
	15	X	13			4	86.7		
	20	X	13					14	404.4
	25	X	13					2	72.2
	40	X	13					3	173.3
	50	X	13					2	144.4
	80	X	13					1	115.6
	150	X	13					1	216.7
	4	X	15	2	13.3				
	4	X	20	2	17.8				
	4	X	30	1	13.3				
	4	X	60					1	26.7
4	X	100					1	44.4	
4	X	120					1	53.3	
DEAN RD. TO WEST END OF PROJECT	6	X	13	52	450.7				
	8	X	13	6	69.3				
	10	X	13	3	43.3				
	15	X	13			6	130.0		
	20	X	13					1	28.9
	25	X	13					2	72.2
	30	X	13					5	216.7
	50	X	13					1	72.2
	80	X	13					2	231.1
	4	X	30	1	13.3				
	4	X	100					1	44.4
SUBTOTALS					2369.3		549.9		2480.0
INCREASE FOR WINTER BREAKUP (5%)					118.5		27.5		124.0
TOTAL					2488		577		2604

CLASS C PATCHES, TYPE II, 12"				
CULVERT STA.	SIZE (FT x FT)			SQ. YD.
	STA. 24+34 LT	8	X	
STA. 24+34 RT	8	X	13	11.6
STA. 41+00 LT	10	X	13	14.4
STA. 41+00 RT	10	X	13	14.4
STA. 101+12 LT	9	X	13	13.0
STA. 101+12 RT	9	X	13	13.0
STA. 110+34.04 LT	9	X	13	13.0
STA. 110+34.04 RT	9	X	13	13.0
STA. 121+02 LT	10	X	13	14.4
STA. 121+02 RT	10	X	13	14.4
STA. 186+71.90 LT	9	X	13	13.0
STA. 186+71.90 RT	9	X	13	13.0
STA. 200+71 LT	8	X	13	11.6
STA. 200+71 RT	8	X	13	11.6
TOTAL				182.0

FILE NAME = miscellaneous.sheet.dgn

USER NAME = russellm
 PLOT SCALE = 100.0000' / IN.
 PLOT DATE = 8/11/2010

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES
 SCALE: SHEET NO. 8 OF 13 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	15W-2,RS-3,16W-3,RS-5	FULTON	171	27
CONTRACT NO. 88098				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				