

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000 FEDERAL PARTICIPATING	Y060 FEDERAL NON-PARTICIPATING
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1	1	
• 60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	2	2	
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	2	2	
• 60240385	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	1	1	
• 60266600	VALVE BOXES TO BE ADJUSTED	EACH	9	9	
• 60500060	REMOVING INLETS	EACH	3	3	
• 60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	1,042	1,042	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,450	2,450	
• 61139800	STORM SEWERS, SPECIAL 4"	FOOT	242	242	
• 61139900	STORM SEWERS, SPECIAL 6"	FOOT	200	200	
67100100	MOBILIZATION	L SUM	1	1	
• 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	33	33	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7,538	7,538	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	536	536	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	165	165	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,144	3,144	
Δ • 72000100	SIGN PANEL - TYPE 1	SQ FT	75	75	
Δ • 72800105	TELESCOPING STEEL SIGN SUPPORT (SPECIAL)	FOOT	72	72	
Δ • 78001100	PAINT PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	33	33	
Δ • 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4,884	4,884	
Δ • 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	536	536	
Δ • 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	141	141	
Δ • 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	
Δ 81017510	CONDUIT IN TRENCH, 1" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	210	210	
Δ 81018500	CONDUIT, PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	485	485	
Δ 81500110	GULFBOX JUNCTION, CAST IRON	EACH	1	1	
Δ 81500120	GULFBOX JUNCTION, COMPOSITE CONCRETE	EACH	2	2	
Δ 81603020	UNIT DUCT, 600V, 3-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	320	320	
Δ 81603047	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	1,765	1,765	
Δ 81603055	UNIT DUCT, 600V, 3-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	445	445	
Δ 81603075	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	555	555	
Δ 81603085	UNIT DUCT, 600V, 3-1C NO.4, GROUND, (XLP-TYPE USE) 1 1/4" DIA. POLYETHYLENE	FOOT	1610	1610	
Δ 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2929	2929	
Δ • 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1	1	
Δ 84200804	REMOVAL OF POLE FOUNDATION	EACH	20	20	
Δ 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1	
• A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	3	3	
• SEE SPECIAL PROVISIONS					
Δ SPECIALITY ITEMS					
(1)NON-PARTICIPATION/ ITEP					

FILE NAME =	USER NAME = jolson	DESIGNED - JRB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CITY OF RUSHVILLE DOWNTOWN SQUARE BRICK STREET RECONSTRUCTION SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
V:\Transportation\2240\22400001.dgn		DRAWN - JMO	REVISED -			N/A	05-00017-00-FP	SCHUYLER	49	4	
	PLOT SCALE = 2.0000' / IN.	CHECKED - JRB	REVISED -			CONTRACT NO. 93541					
	PLOT DATE = 10/22/2010	DATE - 2/12/2010	REVISED -			SCALE: N/A	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 6 [ILLINOIS] FED. AID PROJECT		

Revised 10/29/10