



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 25, 2021

SUBJECT: Route FAS 55 (Center Street)  
Section 18-00026-00-SW (Durand)  
Winnebago County  
Contract No. 85695  
Item 074  
November 5, 2021 Letting  
Addendum C

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised sheets 41 and 68 of the Plans.**
- 2. Revised page 21 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

**PEDESTRIAN RAILING**

This work shall consist of furnishing and installing aluminum pedestrian railing in accordance with the details in the plans and per Section 509 of the IDOT Standard Specifications for Road and Bridge Construction. The railing shall be surface mounted with expansion anchors, include runners, include pickets, include posts and top caps and have a black painted finish. Railing shall not be attached to any of the buildings. Rail height shall be a minimum of 36". All railing heights shall be considered incidental to this pay item. See Sheet 68 of the plans for finish information.

**Method of Measurement.** This work will be measured for payment per FOOT.

**Basis of Payment:** This work will be paid for at the contract unit price per FOOT for PEDESTRIAN RAILING.

**STEEL RAILING REMOVAL**

This work shall consist of removing existing pedestrian railing. Remove all existing handrail as noted on the plans. Existing handrail that is removed shall be disposed of by the Contractor.

**Method of Measurement.** This work will be measured for payment per FOOT.

**Basis of Payment:** This work will be paid for at the contract unit price per FOOT for STEEL RAILING REMOVAL.

**SIDEWALK REMOVAL**

This work shall consist of removing existing concrete sidewalk and concrete steps in accordance with Section 440. This pay item shall include the removal of existing aggregate base and soils to a depth to accommodate the proposed sidewalk section as displayed in the plans. Existing materials shall be disposed of by the Contractor according to the CCDD special provision.

**Method of Measurement.** This work will be measured for payment per SQUARE FOOT.

**Basis of Payment:** This work will be paid for at the contract unit price per SQUARE FOOT for SIDEWALK REMOVAL.

**PAVEMENT REMOVAL**

This work shall conform to Section 440 of the Standard Specifications. The depth of pavement removal shall allow the pavement section detail found in the plans to be constructed. The area of pavement removal shall be according to the plans. This pay item shall include any necessary earth excavation required below the existing pavement that will be removed in order to achieve proper grading per the proposed pavement section. Care must be taken such that bituminous joint faces remain vertical and are protected from spalling. Should the required depth of pavement removal result in the removal of aggregate base or soil, the contractor shall dispose of this excess material according to the CCDD special provision. The Contractor shall be responsible for the removal and disposal of all waste materials.

**Method of Measurement.** This work will be measured for payment per SQUARE YARD.

**Basis of Payment:** This work will be paid for at the contract unit price per SQUARE YARD for PAVEMENT REMOVAL.

**EARTH EXCAVATION**

This work shall conform to Section 202 of the Standard Specifications. It shall consist of the excavation of all soils under full-depth pavement removal, sidewalk removal, and combination curb and gutter removal to achieve the proper depth to install the proposed pavement section, sidewalk section, combination curb and gutter, and walls & footings. The disposal of excess soils generated by excavation shall be paid according to the CCDD special provision.