



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 20, 2021

SUBJECT: Various Routes
Project STP-4LP3(180)
Section D2 SW 2016-1
Henry and Rock Island Counties
Contract No. 64L12
Item No. 95, November 5, 2021 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added pages 78-81 to the Special Provisions.
4. Revised sheets 1, 2, and 4-10 of the Plans.
5. Deleted sheets 16, 17, 30, 43, 73, and 74 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TRAFFIC CONTROL DEVICES - CONES (BDE).....73
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE).....74
WARM MIX ASPHALT (BDE)74
WEEKLY DBE TRUCKING REPORTS (BDE).....75
WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....76
WORKING DAYS (BDE).....77
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC).....78

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)

Description. This work shall consist of the removal and disposal of regulated substances according to Section 669 of the Standard Specifications as revised below.

Contract Specific Work Areas. The excavated soil and groundwater within the work areas listed below shall be managed as either “uncontaminated soil”, hazardous waste, special waste or non-special waste. For stationing, the lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit, whichever is less.

Soil Disposal Analysis. When the waste material requires sampling for landfill disposal acceptance, the Contractor shall secure a written list of the specific analytical parameters and analytical methods required by the landfill. The Contractor shall collect and analyze the required number of samples for the parameters required by the landfill using the appropriate analytical procedures. A copy of the required parameters and analytical methods (from landfill email or on landfill letterhead) shall be provided as Attachment 4A of the BDE 2733 (Regulated Substances Final Construction Report). The price shall include all sampling materials and effort necessary for collection and management of the samples, including transportation of samples from the job site to the laboratory. The Contractor shall be responsible for determining the specific disposal facilities to be utilized; and collect and analyze any samples required for disposal facility acceptance using a NELAP certified analytical laboratory registered with the State of Illinois.

The following contract specific work areas shall be monitored by the Environmental Firm for soil contamination and workers protection.

Site 3616-7 – Casey’s General Store, 103 6th Avenue E., Andalusia, Rock Island County

- All excavation within the northeast corner of 1st Street and 6th Avenue. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-14 – Valley Meats, 2302 1st Street, Coal Valley, Rock Island County

- All excavation within the southwest corner of 23rd Avenue and 1st Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-15 – The Kid’s Corner, 210 1st Street, Coal Valley, Rock Island County

- All excavation within the northwest corner of 23rd Avenue and 1st Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-17 – Shell Gasoline Station, 112 23rd Avenue E., Coal Valley, Rock Island County

- All excavation within the northeast corner of 23rd Avenue and 1st Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Added October 20, 2021

Site 3616-18 – Dental Office of E.E. Martin, 2303 1st Street, Coal Valley, Rock Island County

- All excavation within the southeast corner of 23rd Avenue and 1st Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-20 – Residence, 127 E. 23rd Avenue, Coal Valley, Rock Island County

- All excavation within the southwest corner of 23rd Avenue and 2nd Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-21 – IEFM Consulting Engineers, 128 E. 23rd Avenue, Coal Valley, Rock Island County

- All excavation within the northwest corner of 23rd Avenue and 2nd Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-22 – Commercial building, 2211 E. 2nd Street, Coal Valley, Rock Island County

- All excavation within the northeast corner of 23rd Avenue and 2nd Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-23 – Supreme Services, 203 E. 23rd Avenue, Coal Valley, Rock Island County

- All excavation within the southeast corner of 23rd Avenue and 2nd Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-29 – Alpha Car Wash, 599 N. 1st Street, Alpha, Henry County

- All excavation within the northwest corner of 1st Street and A Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-30 – Alwood Elementary School, 101 E. A Street, Alpha, Henry County

- All excavation within the northeast corner of 1st Street and A Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-32 – Commercial Building, 315 N. 1st Street, Alpha, Henry County

- All excavation within the southeast corner of 1st Street and A Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-33 – Residence, 302 N. 1st Street, Alpha, Henry County

- All excavation within the northwest corner of 1st Street and B Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Added October 20, 2021

Site 3616-39 – Residence, 108 N 1st Street, Alpha, Henry County

- All excavation within the southwest corner of 1st Street and Picard / West-C Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-45 – Residence, 110 S 1st Street, Alpha, Henry County

- All excavation within the northwest corner of 1st Street and E Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-47 – Phillips 66 Gasoline Station, 202 S. 1st Street, Alpha, Henry County

- All excavation within the southwest corner of 1st Street and E Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-50 – Woodhull Municipal Building, 150 N. Division Street, Woodhull, Henry County

- All excavation within the northeast corner of Highway Avenue and Division Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-52 – Clover Township Fire Protection District, 106 E. Highway Avenue, Woodhull, Henry County

- All excavation within the southeast corner of Highway Avenue and Division Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-53 – Woodhull Water Department, 100 block of E. Highway Avenue, Woodhull, Henry County

- All excavation within the northwest corner of Highway Avenue and 3rd Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-54 – Clover Manor Apartments, 150 E. 3rd Street, Woodhull, Henry County

- All excavation within the northeast corner of Highway Avenue and 3rd Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-56 – Commercial Building, 113 S.E. 3rd Street, Woodhull, Henry County

- All excavation within the southeast corner of Highway Avenue and 3rd Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-58 – Mixed Use Building, 542 5th Street, Andover, Henry County

- All excavation within the northeast corner of 5th Street and Mulberry Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Added October 20, 2021

Site 3616-62 – Andover Lake Park, 400 block of 5th Street, Andover, Henry County

- All excavation within the northeast corner of 5th Street and Locust Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-69 – Agricultural Land, 200 block of Main Street, Osco, Henry County

- All excavation within the northeast corner of Main Street and Railroad Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-70 – Farmstead, 203 Main Street, Osco, Henry County

- All excavation within the southwest corner of Main Street and North Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-73 – Mixed Use Building, 221 N. Railroad Street, Osco, Henry County

- All excavation within the northwest corner of Main Street and Railroad Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). COC sampling parameter: VOCs, SVOCs, metals.

Site 3616-75 – Fuel 24 Gasoline Station, 215 Main Street, Osco, Henry County

- All excavation within the southwest corner of Main Street and Railroad Street. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(5). COC sampling parameter: VOCs, SVOCs, metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents, or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), or Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: **None.**

Additional information on the contract specific work areas listed above collected during the regulated substances due-diligence process is available through the District's Environmental Studies Unit (DESU).