

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN 80% FED. 20% STATE	ROADWAY	DRAINAGE (McDONALD CREEK CULVERT)	LIGHTING	CONSTRUCTION TYPE CODE										
					1000-2A	X078-2A	Y030-1E											
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	102		102													
20101100	TREE TRUNK PROTECTION	EACH	7		7													
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	25		25													
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	25		25													
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	25		25													
20101700	SUPPLEMENTAL WATERING	UNIT	6		6													
20200100	EARTH EXCAVATION	CU YD	793		793													
20800150	TRENCH BACKFILL	CU YD	213		213													
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	925		925													
25100630	EROSION CONTROL BLANKET	SQ YD	236		236													
25200110	SODDING, SALT TOLERANT	SQ YD	925		925													
28000400	PERIMETER EROSION BARRIER	FOOT	177		177													
28000510	INLET FILTERS	EACH	38		38													
28200200	FILTER FABRIC	SQ YD	449		449													
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	2,567		2,567													
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	988		988													
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,145		1,145													
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	42		42													
40600895	CONSTRUCTING TEST STRIP	EACH	1		1													
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	97		97													
42001300	PROTECTIVE COAT	SQ YD	1,562		1,562													
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	502		502													
44000100	PAVEMENT REMOVAL	SQ YD	4,149		4,149													
44000600	SIDEWALK REMOVAL	SQ FT	502		502													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3,697		3,697													
44001980	CONCRETE BARRIER REMOVAL	FOOT	95		95													
44003100	MEDIAN REMOVAL	SQ FT	5,614		5,614													
44003800	MEDIAN SURFACE REMOVAL	SQ FT	2,896		2,896													
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	31		31													
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1				1											
50800105	REINFORCEMENT BARS	POUND	121,950				121,950											
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	600				600											
50800515	BAR SPLICERS	EACH	312				312											
51205200	TEMPORARY SHEET PILING	SQ FT	1,338				1,338											