

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN 80% FED. 20% STATE	ROADWAY	DRAINAGE (MCDONALD CREEK CULVERT)	LIGHTING	CONSTRUCTION TYPE CODE										
					1000-2A	X078-2A	Y030-1E											
51500100	NAME PLATES	EACH	1															
54003000	CONCRETE BOX CULVERTS	CU YD	481.3			481.3												
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	26		26													
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	113		113													
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	22		22													
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	63		63													
55100400	STORM SEWER REMOVAL 10"	FOOT	91		91													
55100500	STORM SEWER REMOVAL 12"	FOOT	48		48													
55101200	STORM SEWER REMOVAL 24"	FOOT	22		22													
55102000	STORM SEWER REMOVAL 54"	FOOT	63		63													
60201205	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 12 FRAME AND GRATE	EACH	2		2													
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1													
60236900	INLETS, TYPE A, TYPE 12 FRAME AND GRATE	EACH	1		1													
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	34		34													
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	4		4													
60500040	REMOVING MANHOLES	EACH	1		1													
60500050	REMOVING CATCH BASINS	EACH	2		2													
60500060	REMOVING INLETS	EACH	1		1													
60618200	BITUMINOUS MEDIAN SURFACE	SQ FT	5,207		5,207													
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	3,068		3,068													
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	3,528		3,528													
60624600	CORRUGATED MEDIAN	SQ FT	1,102		1,102													
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1		1													
63200310	GUARDRAIL REMOVAL	FOOT	454		454													
63700255	CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT	FOOT	95		95													
66400105	CHAIN LINK FENCE, 4'	FOOT	69		69													
66400525	CHAIN LINK FENCE, 4' ATTACHED TO STRUCTURE	FOOT	26			26												
66410300	CHAIN LINK FENCE REMOVAL	FOOT	96		96													
66700095	PERMANENT SURVEY MARKERS	EACH	1		1													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6													
67100100	MOBILIZATION	L SUM	1.0		1.0													
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0		1.0													
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12		12													
70400100	TEMPORARY CONCRETE BARRIER	FOOT	457		457													

** Specialty Items*

FILE NAME =
G:\projects\2002305\CADD\Civil\Sheet\002\02PLM\SM_01.dgn

USER NAME = zpiend
PLOT SCALE = 50.0000' / IN.
PLOT DATE = 8/11/2009

DESIGNED - DLP
DRAWN - ENTRAN
CHECKED - TMH
DATE - 03/09

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**MCDONALD CREEK CULVERT
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 305	SECTION 0913.1-T	COUNTY COOK	TOTAL SHEETS 39	SHEET NO. 4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60E53	