

SCHEDULE OF QUANTITIES

60500040 REMOVING MANHOLES

STATION	OFFSET(FT)	EACH
PALATINE ROAD		
348+02.3	38.8 LT	1.0
TOTAL = 1		

60500050 REMOVING CATCH BASINS

STATION	OFFSET(FT)	EACH
PALATINE ROAD		
348+39.0	25.7 RT	1.0
349+15.5	65.2 RT	1.0
TOTAL = 2		

60500060 REMOVING INLETS

STATION	OFFSET(FT)	EACH
PALATINE ROAD		
347+85.7	64.5 LT	1.0
TOTAL = 1		

60618200 HOT-MIX ASPHALT MEDIAN SURFACE

STATION	WIDTH(FT)	STATION	WIDTH(FT)	SQ FT
PALATINE ROAD				
342+01.6	2.8	344+05.8	2.3	523.7
344+05.8	2.3	348+74.9	14.7	3,987.7
348+74.9	14.7	349+34.4	8.7	695.3
TOTAL = 5,207				

60618300 CONCRETE MEDIAN SURFACE, 4 INCH

STATION	WIDTH(FT)	STATION	WIDTH(FT)	SQ FT
PALATINE ROAD				
347+76.3	8.7	349+43.1	15.0	1,976.9
349+43.1	15.0	350+21.5	12.8	1,091.2
TOTAL = 3,068				

60619600 CONCRETE MEDIAN, TYPE SB-6.12

STATION	WIDTH(FT)	STATION	WIDTH(FT)	SQ FT
PALATINE ROAD				
NORTH SIDE - MAINLINE				
342+46.7	6.0	345+85.2	6.0	2,030.7
346+72.3	4.0	347+76.9	11.9	831.3
SOUTH SIDE - MAINLINE				
349+33.9	12.2	350+16.1	4.0	665.7
TOTAL = 3,528				

60624600 CORRUGATED MEDIAN

STATION	WIDTH(FT)	STATION	WIDTH(FT)	SQ FT
PALATINE ROAD				
NORTH SIDE - MAINLINE				
345+85.2	6.0	346+15.3	4.0	150.8
SOUTH SIDE - MAINLINE				
350+92.0	8.0	351+71.3	16.0	951.5
TOTAL = 1,102				

63100169 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED

STATION	OFFSET(FT)	EACH
PALATINE ROAD		
SOUTH SIDE - MAINLINE		
354+36.2	27.6 RT	1.0
TOTAL = 1		

63200310 GUARDRAIL REMOVAL

STATION	OFFSET(FT)	STATION	OFFSET(FT)	FOOT
PALATINE ROAD				
NORTH SIDE - MAINLINE				
349+38.9	35.8 LT	350+39.9	35.3 LT	101.0
349+38.7	32.9 LT	350+40.1	32.2 LT	101.4
SOUTH SIDE - MAINLINE				
346+77.6	30.6 RT	347+78.4	33.0 RT	100.8
346+77.7	33.0 RT	347+78.8	36.0 RT	101.1
353+86.2	27.7 RT	354+36.2	27.6 RT	50.0
TOTAL = 454				

63700255 CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT

STATION	OFFSET(FT)	STATION	OFFSET(FT)	FOOT
PALATINE ROAD				
CENTERLINE				
347+97.2	0.0 RT	348+91.8	0.0 RT	94.7
TOTAL = 95				

66400105 CHAIN LINK FENCE, 4'

STATION	OFFSET(FT)	STATION	OFFSET(FT)	FOOT
PALATINE ROAD				
SOUTH SIDE - FRONTAGE ROAD				
348+51.5	81.2 RT	348+78.8	81.2 RT	27.3
349+04.7	81.1 RT	349+14.6	81.1 RT	9.9
349+14.6	81.1 RT	349+45.8	75.0 RT	31.9
TOTAL = 69				

66410300 CHAIN LINK FENCE REMOVAL

STATION	OFFSET(FT)	STATION	OFFSET(FT)	FOOT
PALATINE ROAD				
SOUTH SIDE - FRONTAGE ROAD				
348+51.5	77.4 RT	349+01.0	77.3 RT	49.5
349+01.0	77.3 RT	349+09.4	81.1 RT	9.2
349+09.4	81.1 RT	349+20.9	75.9 RT	12.6
349+20.9	75.9 RT	349+45.8	75.0 RT	25.0
TOTAL = 96				

70400100 TEMPORARY CONCRETE BARRIER

STATION	OFFSET(FT)	STATION	OFFSET(FT)	FOOT
PALATINE ROAD				
MOT STAGE 1				
NORTH SIDE				
347+73.5	40.0 LT	349+15.1	40.0 LT	141.6
349+15.1	40.0 LT	350+12.3	27.6 LT	98.0
SOUTH SIDE				
347+04.5	30.3 RT	348+00.3	39.9 RT	96.3
348+00.3	39.9 RT	349+21.6	40.2 RT	121.3
TOTAL = 457				

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

STATION	OFFSET(FT)	STATION	OFFSET(FT)	FOOT
PALATINE ROAD				
MOT STAGE 2				
NORTH SIDE				
347+81.1	25.2 LT	349+30.0	25.2 LT	148.9
349+30.0	25.2 LT	349+96.6	43.0 LT	69.0
SOUTH SIDE				
347+29.2	42.0 RT	348+18.4	25.3 RT	90.7
348+18.4	25.3 RT	349+09.2	25.4 RT	90.8
TOTAL = 399				

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

STATION	OFFSET(FT)	STATION	OFFSET(FT)	FOOT
PALATINE ROAD				
NORTH SIDE - FRONTAGE ROAD CENTERLINE - WHITE				
342+01.6	41.0 LT	345+82.3	41.0 LT	95.2
349+01.2	53.0 LT	356+00.0	53.0 LT	174.7
NORTH SIDE - MAINLINE EDGE LINE - WHITE				
342+01.6	24.0 LT	345+83.4	24.0 LT	381.8
349+43.0	26.0 LT	356+00.0	26.0 LT	657.0
NORTH SIDE - MAINLINE CENTERLINE - WHITE				
342+01.6	13.2 LT	356+00.0	13.4 LT	349.6
NORTH SIDE - MAINLINE EDGE LINE - YELLOW				
342+01.6	1.2 LT	356+00.0	1.2 LT	1,398.4
SOUTH SIDE - MAINLINE EDGE LINE - YELLOW				
342+01.6	1.2 RT	356+00.0	1.2 RT	1,398.4
SOUTH SIDE - MAINLINE CENTERLINE - WHITE				
342+01.6	13.5 RT	356+00.0	12.8 RT	349.6
SOUTH SIDE - MAINLINE EDGE LINE - WHITE				
342+01.6	24.0 RT	348+74.6	26.1 RT	673.0
351+71.3	26.0 RT	356+00.0	26.0 RT	428.7
SOUTH SIDE - FRONTAGE ROAD CENTERLINE - WHITE				
342+01.6	41.0 RT	349+05.9	56.0 RT	176.1
351+71.2	53.0 RT	356+00.0	53.0 RT	107.2
TOTAL = 6,190				

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

STATION	OFFSET(FT)	STATION	OFFSET(FT)	FOOT
PALATINE ROAD				
NORTH SIDE - GORE AREA - WHITE				
345+82.3	30.0 LT	346+84.5	24.0 LT	102.4
345+82.3	24.3 LT	346+84.5	24.0 LT	102.2
346+28.3	44.2 LT	347+46.4	47.6 LT	118.1
346+28.3	44.2 LT	349+43.0	26.0 LT	315.3
SOUTH SIDE - GORE AREA - WHITE				
348+74.6	26.1 RT	350+54.0	48.0 RT	180.7
349+06.2	45.0 RT	350+54.0	48.0 RT	147.8
350+20.4	26.0 RT	351+71.3	26.0 RT	150.9
350+20.4	26.0 RT	351+71.2	42.0 RT	151.6
TOTAL = 1,269				

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

STATION	OFFSET(FT)	STATION	OFFSET(FT)	FOOT
PALATINE ROAD				
NORTH SIDE - FRONTAGE ROAD STOP BAR - WHITE				
346+74.2	60.4 LT	346+74.2	45.5 LT	14.9
SOUTH SIDE - FRONTAGE ROAD STOP BAR - WHITE				
350+12.4	47.2 RT	350+12.4	64.0 RT	16.8
TOTAL = 32				