

SUMMARY OF TRAFFIC SIGNAL QUANTITIES					
DESIGNATION	UNIT	TOTAL QUANTITIES	SCHOENBECK ROAD @ PALATINE ROAD	ILL. RTE. 83 (ELMHURST RD.) @ PALATINE ROAD	INTERCONNECT
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	134	-	-	134
HANDHOLE	EACH	2	-	-	2
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	111	-	-	111
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	1	1	-
MODIFY EXISTING CONTROLLER	EACH	2	1	1	-
REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1264	-	-	1264
REMOVE EXISTING HANDHOLE	EACH	1	-	-	1
WIRELESS INTERCONNECT (COMPLETE)	EACH	2	1	1	-

FILE NAME = #FILEL#	USER NAME = #USER#	DESIGNED - PKG DRAWN - MAA, SHM	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES INTERCONNECT SCHOENBECK ROAD AT ILLINOIS ROUTE 83 (ELMHURST RD.)	F.A.P. RTE. 305	SECTION 0913.1-T	COUNTY COOK	TOTAL SHEETS 39	SHEET NO. 18A	
PLOT SCALE = #SCALE#	CHECKED - PKG	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			
PLOT DATE = #DATE#	DATE -	REVISED -	CONTRACT NO. 60E53								