

SUMMARY OF QUANTITIES

PROJECT NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332/874	2002-113R	WILL	242	3
STA.		TO STA.		
EXISTING CONDITIONS:				

CODE NO	ITEM	UNIT	LIRBAW 80% FED. 20% STATE TOTAL QUANTITIES	ACF			100% CRETE											
				ACF ROADWAY I000-2A	ACBHF BRIDGE X071-2A	TRAFFIC SYGNAL GOODENOW RD Y031-1F	TRAFFIC SIGNAL IL-394 Y031-1F	TRAFFIC SIGNAL INTERCONNECT Y031-1F	CRETE TOWNSHIP FIRE DEPT Y031-3D	100% STATE LIGHTING Y030-1E	ACBHF NOISE WALL 80% FED/20% STATE I000-2A							
MX281003	STONE RIPRAP, CLASS C3	SQ M	87	87														
M2800305	TEMPORARY DITCH CHECKS	METER	7		7													
28000500	INLET AND PIPE PROTECTION	EACH	1		1													
28000510	INLET FILTERS	EACH	3	3														
M4402060	APPROACH SLAB REMOVAL	SQ M	444.0		444.0													
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1														
50104900	REMOVAL OF EXISTING SUB-STRUCTURES	EACH	2	2														
50101600	REMOVAL OF EXISTING SUPERSTRUCTURES	L SUM	1		1													
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1													
50300100	FLOOR DRAINS	EACH	11		11													
50500505	STUD SHEAR CONNECTORS	EACH	5808		5808													
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12		12													
50501005	JACK AND REPOSITION BEARINGS	EACH	12		12													
50800515	BAR SPLICERS	EACH	136		136													
51500100	NAME PLATES	EACH	2		2													
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	19		19													
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	7		7													
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	7	2	5													
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	10	5	5													
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	5	5														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12														
67100100	MOBILIZATION	L SUM	1	0.5	0.5													
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.5	0.5													
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	510	510														
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5	5														
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	410	410														
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1								1							
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1								1							
* 81400100	HANDHOLE	EACH	3				3											
* 81400200	HEAVY-DUTY HANDHOLE	EACH	22			9	8	5										
* 81400300	DOUBLE HANDHOLE	EACH	2			1	1											
* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	25								25							
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	12								12							
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	14								14							
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	4								4							
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	14								14							

*Specialty Items