

# SUMMARY OF QUANTITIES

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332/876	2002-113R	WILL	242	9
STA.		TO STA.		
EXISTING CONDITIONS:				

SUMMARY OF QUANTITIES			L.I.B.A.N. 80% FED. 20% STATE TOTAL QUANTITIES	ACF			100% CRETE			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		ACF ROADWAY 1000-2A	ACBHF BRIDGE X071-2A	TRAFFIC SYGNAL GOODENOW RD Y031-1F	TRAFFIC SIGNAL IL-394 Y031-1F	TRAFFIC SIGNAL INTERCONNECT Y031-1F	CRETE TOWNSHIP FIRE DEPT Y031-3D	100% STAFFE LIGHTING Y030-1E	ACBHF NOISE WALL 80% FED, 20% STATE 1000-2A		
M8160400	UNIT DUCT, WITH 3-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 30MM DIA., POLYETHYLENE	METER	1620					1620					
M8160415	UNIT DUCT, WITH 3-1/C NO. 2 AND 1/C NO. 4 GROUND, 600V (EPR-TYPE RHW), 40MM DIA., POLYETHYLENE	METER	1344						1344				
M8170870	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C 350MCM	METER	15						15				
M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	2392			178	338	788		1088			
M8305050	LIGHT POLE, ALUMINUM, 14.5M M.H., 4.5M MAST ARM	EACH	4						4				
M8380095	BREAKAWAY DEVICE, TRANSFORMER BASE, 381MM BOLT CIRCLE	EACH	13					9		4			
M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	224.3						224.3				
M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	1830.5			943.2	887.3						
M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	738.7			266.3	472.4						
M8731300	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	METER	2161			773.7	1387.3						
M8731800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	METER	46.5			30.5	16						
M8750110	TRAFFIC SIGNAL POST, 4.85 METER	EACH	3			2	1						
M8770777	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 14.02 METER	EACH	1			1							
M8780100	CONCRETE FOUNDATION, TYPE A	METER	36			24	12						
M8780150	CONCRETE FOUNDATION, TYPE C	METER	24			12	12						
M8860100	DETECTOR LOOP, TYPE I	METER	374.8			201	173.8						
MX030199	TEMPORARY PAVEMENT	SQ M	2210	2210									
MX030217	PIPE CULVERT REMOVAL 375MM	METER	100	100									
MX030218	PIPE CULVERT REMOVAL 450MM	METER	30	30									
MX030355	NOISE ABATEMENT WALL, GROUND MOUNTED	SQ M	2210							2210			
* MX032073	AERIAL CABLE, 3-1/C NO. 2, ALUMINUM, WITH MESSENGER WIRE	METER	1097						1097				
* MX032680	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	KG	13	13									
* MX032723	PREFORMED DETECTOR LOOP	METER	197.8				197.8						
* MX032819	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	METER	920.4					920.4					
* MX032922	ELECTRIC CABLE IN CONDUIT, GROUNDING NO. 6 1C	METER	458.8			235.3	223.5						
* MX033189	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL	LITER	0.3	0.3									
MX033693	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 125 MM)	SQ M	195		195								
MX033694	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 125 MM)	SQ M	8.91		8.91								
* MX033724	GROUND ROD 16MM DIA. X 3.0M	EACH	12						12				
* MX843010	REMOVE EXISTING CONDUIT ATTACHED TO STRUCTURE	METER	60						60				

\*Specialty Items