

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B-1	DU PAGE	117	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT #62881

J000-2A

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE					100% ITASCA
				RDWY	BRIDGE	LANDSCAPING	RETAINING WALL	GUARD RAIL	TRAFFIC SIGNAL
				J000-2A	X071-2A				Y031-1F
28000500	INLET AND PIPE PROTECTION	EACH	1	1					
28000510	INLET FILTERS	EACH	30	30					
28100107	STONE RIPRAP, CLASS A4	SQ YD	784		784				
28200200	FILTER FABRIC	SQ YD	839		839				
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	817	817					
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	79	79					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2					
40600300	AGGREGATE (PRIME COAT)	TON	3	3					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	66	66					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	76	76					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	7	7					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	141	141					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	115	115					
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	8,870	8,870					
42001300	PROTECTIVE COAT	SQ YD	19,536	19,536					
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	468	468					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	680	680					
42400800	DETECTABLE WARNINGS	SQ FT	50	50					
44000100	PAVEMENT REMOVAL	SQ YD	8,417	8,417					
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	919	919					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	677	677					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	797	797					
44000600	SIDEWALK REMOVAL	SQ FT	667	667					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	37	37					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	28	28					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	443	443					
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1				

\* SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
ILLINOIS ROUTE 53 (FAU 2578)

SUMMARY OF QUANTITIES

SCALE: NONE

DRAWN BY: CPK

DATE: 6/12/09

CHECKED BY: JJC