

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B-1	DU PAGE	117	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT #62881

J000-2A

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE					100% ITASCA
				RDWY	BRIDGE	LANDSCAPING	RETAINING WALL	GUARD RAIL	TRAFFIC SIGNAL
				J000-2A	X071-2A				Y031-1F
50105220	PIPE CULVERT REMOVAL	FOOT	205	205					
50200100	STRUCTURE EXCAVATION	CU YD	473		193		280		
50300100	FLOOR DRAINS	EACH	4		4				
50300225	CONCRETE STRUCTURES	CU YD	182.7		68.1		114.6		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	209.9		209.9				
50300260	BRIDGE DECK GROOVING	SQ YD	429		429				
50300300	PROTECTIVE COAT	SQ YD	763		592		171		
50300510	RUSTICATION FINISH	SQ FT	1,542				1,542		
50300285	FORM LINER TEXTURED SURFACE	SQ FT	1,542				1,542		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1				
50500505	STUD SHEAR CONNECTORS	EACH	3,553		3,201		352		
* 50700209	UNTREATED TIMBER LAGGING	SQ FT	1,857				1,857		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	59,690		47,580		12,110		
50800515	BAR SPLICERS	EACH	395		395				
50900105	ALUMINUM RAILING, TYPE L	FOOT	99		99				
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1,768		1,768				
* 51202210	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	1,011				1,011		
51202305	DRIVING PILES	FOOT	1,768		1,768				
51203600	TEST PILE STEEL HP12X53	EACH	1		1				
51204650	PILE SHOES	EACH	28		28				
51500100	NAME PLATES	EACH	2		1		1		
52100520	ANCHOR BOLTS , 1"	EACH	44		44				
54001000	BOX CULVERT END SECTIONS	EACH	2	2					
54010403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT	94	94					
54200430	PIPE CULVERTS, TYPE 1 RCCP 15"	FOOT	47	47					
54201270	PIPE CULVERTS TYPE 2 RCCP 15"	FOOT	104	104					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	7	7					
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1					

* SPECIALTY ITEM

6/10/2009 5:04:52 PM PDF(Grey_Large).plt Q:\DOT\9356_A0_ILL53\Springbrook\Drawings\RDWY\shfts\RDV\S_Soc.dgn



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 53 (FAU 2578)

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 6/12/09

DRAWN BY: CPK
CHECKED BY: JJC

Rev.