F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B	DUPAGE	117	116
STA. 10+60.49 TO 11+16.66				
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT #62881

75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75

695 690 685

℄ BALL PARK ENTRANCE

690.57 690.79 690.57

1:50 -2.00 % -2.00 % 1:50

1:3 1:3

Drop Drop

11 + 16.66

STAGE 1

11+16.66	CUT	0.00
	FILL	39.63

ALL UNITS ARE SQ FT

℄ BALL PARK ENTRANCE

691.06 691.28 691.06

1:50 -2.00 % -2.00 % 1:50

1:3 1:3

Drop Drop

10 + 99.93

STAGE 1

10+99.93	CUT	0.00
	FILL	50.42

ALL UNITS ARE SQ FT

℄ BALL PARK ENTRANCE

692.18 692.43 692.19

1:50.17 -2.17 % -2.00 % 1:52.19

1:3.01 1:3.13

Drop Drop

10 + 60.49

STAGE 1

10+60.49	CUT	0.00
	FILL	103.14

ALL UNITS ARE SQ FT

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

PAVEMENT REMOVAL

SCALE: 1"=10' HORIZ.
1"=5' VERT.

BALL PARK ENTRANCE

BY	DATE
ORIGINAL SURVEY	SURVEYED
	PLOTTED
NOTE BOOK	PHASE
	AREAS
NO.	AREAS CHECKED

BY	DATE
FINAL SURVEY	SURVEYED
	PLOTTED
NOTE BOOK	PHASE
	AREAS
NO.	AREAS CHECKED

PATRICK ENGINEERING INC.
LISLE, ILLINOIS