

F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00199-00-LS	COOK	19	2
<b>SUMMARY OF QUANTITIES</b>				
			ILLINOIS	6304

<b>SUMMARY OF QUANTITIES</b>				
NO.	CODE NO.	PAY ITEM	UNIT	TOTAL
1	20101700	SUPPLEMENTAL WATERING	UNIT	2
2	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	15
3	20700220	POROUS GRANULAR EMBANKMENT	CU YD	15
4	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	400
5	35200600	EARTH EXCAVATION	CU YD	65
6	35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SQ YD	31
7	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10
8	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	4
9	42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	2450
10	44000100	PAVEMENT REMOVAL	SQ YD	31
11	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	275
12	44000600	SIDEWALK REMOVAL	SQ FT	2477
13	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 6.12	FOOT	275
14	60625900	P.C.C. RAMPED MEDIAN TERMINAL	EACH	1
15	67100100	MOBILIZATION	L SUM	1
16	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
17	80400100	ELECTRIC SERVICE INSTALLATION	EACH	3
18	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
19	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	3,975
20	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1
* 21	82500505	LIGHTING CONTROLLER, SPECIAL	EACH	5
* 22	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	916
* 23	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	138
24	84200700	LIGHTING FOUNDATION REMOVAL	EACH	138
25	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	20
26	X0301766	DRILL AND GROUT #6 TIE BARS	EACH	280
* 27	XX003313	REMOVE AND REINSTALL BRICK PAVER	SQ FT	3,000
* 28	XX007584	CONDUIT, BORED AND PULLED, GALVANIZED STEEL, 2", SPECIAL	FOOT	6,100
29	Z0062450	SAWING PAVEMENT (FULL DEPTH)	FOOT	290
* 30	XX008174	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 4/C NO. 6 & 1/C NO. 8 GROUND, SPECIAL	FOOT	1,675
* 31	XX008175	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 7/C NO. 6 & 1/C NO. 8 GROUND, SPECIAL	FOOT	4,170
* 32	XX008176	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 9/C NO. 6 & 1/C NO. 8 GROUND, SPECIAL	FOOT	705
* 33	XX008176	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 10/C NO. 6 & 1/C NO. 8 GROUND, SPECIAL	FOOT	3,440
* 34	XX008178	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 11/C NO. 6 & 1/C NO. 8 GROUND, SPECIAL	FOOT	60
* 35	XX008179	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 12/C NO. 6 & 1/C NO. 8 GROUND, SPECIAL	FOOT	95
* 36	XX008180	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 13/C NO. 6 & 1/C NO. 8 GROUND, SPECIAL	FOOT	1,205
* 37	XX008181	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 3/C NO. 2 & 1/C NO. 8 GROUND, SPECIAL	FOOT	130
* 38	XX008182	LIGHT POLE, ALUMINUM, 14 FT. M.H., 3 FT. MAST ARM, WITH 150W MH LUMINAIRE, SPECIAL	EACH	95
* 39	XX008183	LIGHT POLE, ALUMINUM, 30 FT. M.H., 6 FT. MAST ARM, WITH 250W MH LUMINAIRE, SPECIAL	EACH	34
* 40	XX008184	LIGHT POLE, ALUMINUM, 30 FT. M.H., DUAL 6 FT. MAST ARMS, WITH TWO 250W MH LUMINAIRES, SPECIAL	EACH	9
* 41	XX006344	SODDING (COMPLETE)	SQ YD	30
* 42	XX000959	TRASH RECEPTACLES	EACH	10
* 43	XX044100	BENCHES	EACH	10

\* PAY ITEM IS SUPPLEMENTED OR COVERED WITHIN THE SPECIAL PROVISIONS

PLANS PREPARED BY:  
**GEWALT HAMILTON**  
 ASSOCIATES, INC.  
 Consulting Engineers & Surveyors  
 650 Forest Ridge Drive  
 Vernon Hills, IL 60061  
 (847) 478-9700  
 (847) 478-9701 Fax

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 DES PLAINES LIGHTING IMPROVEMENTS  
 AND STREETSCAPE  
 DES PLAINES, ILLINOIS  
 SCALE: 1"=40'  
 DATE: 8-14-2009  
 DRAWN BY: DRS  
 DESIGNED BY: AJP  
 CHECKED BY: BLS

10-000-00000-1-1000