

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	00-00242-00-CH	COOK	129	4
STA.	TO STA.			
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES				1000-2A ROADWAY SKOKIE 70% STU 30% STATE	1000-2A ROADWAY IN-LINE DETENTION 70% STU \$40K STATE 30%-\$40K LA	Y030-1E LIGHTING SKOKIE 70% STU 30% LA	Y031-1F SIGNALS FOSTER 70% STU 15% STATE 15% LA	Y031-1F SIGNALS GOLF 70% STU 30% STATE	Y031-1F SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	Y031-1F SIGNALS INTERCONNECT 70% STU 30% STATE	Y060 WATER SKOKIE NON-PART 100% LA	Y031-1F SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY									
20100110	* TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12		12							
20100210	* TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	17		17							
20101000	TEMPORARY FENCE	FOOT	1,440		1,440							
20101200	* TREE ROOT PRUNING	EACH	36		36							
20101300	* TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	36		36							
20200100	EARTH EXCAVATION	CU YD	7,437		7,437							
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,029		1,029							
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	600		600							
20800150	TRENCH BACKFILL	CU YD	4,026		550	3,050					426	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,800		1,800							
21101615	* TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,601		1,601							
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	200		200							
25000400	* NITROGEN FERTILIZER NUTRIENT	POUND	20		20							
25000500	* PHOSPHORUS FERTILIZER NUTRIENT	POUND	20		20							
25000600	* POTASSIUM FERTILIZER NUTRIENT	POUND	20		20							
25101504	* WOOD CHIP MULCH 4"	SQ YD	50		50							
25200110	* SODDING, SALT TOLERANT	SQ YD	1,601		1,601							
25200200	* SUPPLEMENTAL WATERING	UNIT	14		14							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	33		33							
28000400	PERIMETER EROSION BARRIER	FOOT	300		300							
28000510	INLET FILTERS	EACH	63		63							
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1,879		1,879							
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	19,700		19,700							
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	14,323		14,323							
35301200	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	3,073		3,073							
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	178		178							
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	39		39							
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,510		4,510							
40600300	AGGREGATE (PRIME COAT)	TON	90		90							
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	215		215							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	202		202							
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	166		24	68					74	
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	2,275		2,275							
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5		5							

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SKOKIE BOULEVARD (U.S. ROUTE 41)  
  
SUMMARY OF QUANTITIES  
  
DATE 11-14-08  
DRAWN BY CEC  
CHECKED BY DWB  
  
NOT TO SCALE

PLOT DATE = 11/14/2008  
FILE NAME = #FILE#  
PLOT SCALE = #SCALE#  
USER NAME = #USER#