

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
350	00-00242-00-CH	COOK	129	8
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES				1000-2A ROADWAY SKOKIE 70% STU 30% STATE	1000-2A ROADWAY IN-LINE DETENTION 70% STU \$40K STATE 30%-\$40K LA	Y030-1E LIGHTING SKOKIE 70% STU 30% LA	Y031-1F SIGNALS FOSTER 70% STU 15% STATE 15% LA	Y031-1F SIGNALS GOLF 70% STU 30% STATE	Y031-1F SIGNALS SOUTH MALL ENTRANCE 70% STU 30% STATE	Y031-1F SIGNALS INTERCONNECT 70% STU 30% STATE	Y060 WATER SKOKIE NON-PART 100% LA	Y031-1F SIGNALS EMERGENCY VEHICLE PREEMPTION 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY									
81702150	* ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	20			20						
81800200	* AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	4,595			4,595						
81900200	* TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6,236			2,889	96	1,601	318	1,332		
83009600	* LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. MAST ARM	EACH	16			16						
83057300	* LIGHT POLE, WOOD, 55 FOOT, CLASS 3	EACH	12			12						
83057305	* LIGHT POLE, WOOD, 55 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	16			16						
83600200	* LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	128			128						
84200500	* REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	18			18						
84200700	* LIGHTING FOUNDATION REMOVAL	EACH	19			19						
84400105	* RELOCATE EXISTING LIGHTING UNIT	EACH	1			1						
84500110	* REMOVAL OF LIGHTING CONTROLLER	EACH	1			1						
85000200	* MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4						1	3		
85700205	* FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2				1	1				
86000100	* MASTER CONTROLLER	EACH	1							1		
86400100	* TRANSCEIVER - FIBER OPTIC	EACH	2							2		
87301215	* ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2,333				637	1,696				
87301225	* ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3,877				1,964	1,913				
87301245	* ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4,488				2,080	2,408				
87301255	* ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,853				815	2,038				
87301305	* ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	5,057				3,543	1,514				
87301805	* ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	298				73	225				
87702810	* STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 16 FT.	EACH	2					2				
87702830	* STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 20 FT.	EACH	1					1				
87702850	* STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT.	EACH	1					1				
87702950	* STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	2					2				
87702990	* STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	2					2				
87704320	* STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 24 FT. AND 32 FT.	EACH	1				1					
87800150	* CONCRETE FOUNDATION, TYPE C	FOOT	8				4	4				
87800415	* CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	180				60	120				
87900200	* DRILL EXISTING HANDHOLE	EACH	6						2	4		
88030020	* SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	20				10	10				
88030110	* SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	12				4	8				
88102717	* PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8					8				
88102747	* PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4				4					

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SKOKIE BOULEVARD (U.S. ROUTE 41)

SUMMARY OF QUANTITIES

PLOT DATE = 11/14/2008
PLOT SCALE = AS SHOWN
USER NAME = RUSER88