

SCHEDULE OF RELOCATE SIGN PANEL ASSEMBLY - TYPE A	
PROPOSED LOCATION	TELESCOPING STEEL SIGN SUPPORT (FT)
STA. 63+02, 46' LT.	-
STA. 65+50, 30' RT.	14'
STA. 67+50, 49' LT.	14'

SCHEDULE OF SIGN PANEL - TYPE 1				
PROPOSED LOCATION	SIGN NUMBER	DIMENSIONS	AREA (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (FT)
STA. 81+27, 49' LT.	R1-1	30" x 30"	6.25	14'
SCHEDULE OF SIGN PANEL - TYPE 2 ONLY IF NEEDED				

EARTHWORK SCHEDULE VIRGINIA ROAD				
ITEM	UNIT	TOTAL	PHASE I (WEST)	PHASE II (EAST)
EARTH EXCAVATION	C.Y.	9,035	4,560	4,475
FURNISHED EXCAVATION	C.Y.	304	201	103
FURNISHED EXCAVATION ADJUSTED FOR SHRINKAGE	C.Y.	380	251	129
EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	C.Y.	+8,871	+4,610	+4,261
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL				
UNDERCUT	C.Y.	2,800	1,400	1,400

UNDERCUT DEPTH SCHEDULE*		
FROM	TO	DEPTH
21+00	26+50	1'
57+00	73+50	1'

* STATIONS AND DEPTHS ARE APPROXIMATE.
FINAL LOCATIONS AND DEPTHS WILL BE
DETERMINED IN THE FIELD BY THE ENGINEER.

NOTE: SHRINKAGE CALCULATED USING 25% SHRINKAGE FACTOR (PER IDOT LRS*2)

Revised 10-22-09

FILE NAME =	USER NAME = ara	DESIGNED - RJD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
J:\2211\road\sheet\2211-shr-schedule.qnty.dgn		DRAWN - ARA	REVISED -			0121	09-00362-00-PV	MCHENRY	54	7
PLOT SCALE = 1:8000 1/4 IN.		CHECKED - GAB	REVISED -			CONTRACT NO. 63195				
PLOT DATE = 10/21/2009		DATE - 5-28-09	REVISED -			SCALE: N.T.S.	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.