

SUMMARY OF QUANTITIES				I000-2A ROADWAY STA 116+00 TO STA 129+61 80% HBP 20% COUNTY	I000-2A ROADWAY STA 106+25 TO STA 116+00 100% COUNTY	X081-2A BRIDGE S.N. 056-3174 80% HBP 20% COUNTY
CODE NO	PAY ITEM	UNIT	QUANTITY			
40600300	AGGREGATE (PRIME COAT)	TON	14	7	7	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	90	47	43	
40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SQ YD	6,928	3,424	3,504	
42001300	PROTECTIVE COAT	SQ YD	2,800	1,138	1,662	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	46	46		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	227	186	41	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	59		59	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	11,764	4,075	7,689	
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	52	52		
42400800	DETECTABLE WARNINGS	SQ FT	107		107	
44000100	PAVEMENT REMOVAL	SQ YD	7,149	4,023	3,126	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	777	406	371	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	976	323	653	
44000300	CURB REMOVAL	FOOT	19	19		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,760	913	847	
44000600	SIDEWALK REMOVAL	SQ FT	8,141	2,143	5,998	
44004000	PAVED DITCH REMOVAL	FOOT	119	119		
44004250	PAVED SHOULDER REMOVAL	SQ YD	278	61	217	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	249	249		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	624	624		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1
50104400	CONCRETE HEADWALL REMOVAL	EACH	2			2
50105220	PIPE CULVERT REMOVAL	FOOT	238	115	123	
50200100	STRUCTURE EXCAVATION	CU YD	304			304
50300225	CONCRETE STRUCTURES	CU YD	64.3			64.3
50300254	RUBBED FINISH	SQ FT	1,423			1,423
50300255	CONCRETE SUPERSTRUCTURE	CU YD	224.9			224.9
50300260	BRIDGE DECK GROOVING	SQ YD	507			507
50300300	PROTECTIVE COAT	SQ YD	629			629
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	398			398
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	58,530			58,530
50800515	BAR SPLICERS	EACH	503			503
50901125	STEEL RAILING (TEMPORARY)	FOOT	30			30
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	840			840

• SPECIALTY ITEM