

SUMMARY OF QUANTITIES					I000-2A ROADWAY STA 116+00 TO STA 129+61 80% HBP 20% COUNTY	I000-2A ROADWAY STA 106+25 TO STA 116+00 100% COUNTY	X081-2A BRIDGE S.N. 056-3174 80% HBP 20% COUNTY
CODE NO	PAY ITEM	UNIT	QUANTITY				
* 89501510	RELOCATE EXISTING FLASHING BEACON	EACH	1			1	
* A2002520	TREE, CARPINUS CAROLINIANA (AMERICAN HORNBEAM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3	3			
* A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2			
* A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2			
* A2006420	TREE, QUERCUS ALBA (WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2			
* A2006720	TREE, QUERCUS MACROCARPA (BUR OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	1	1		
* A2015990	TREE, FAGUS SYLVATICA, EUROPEAN BEECH, 1-1/2" BALLED AND BURLAPPED	EACH	1	1			
* B2001620	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 2-1/2" CALIPER TREE FORM, BALLED AND BURLAPPED	EACH	3	3			
X0300057	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	3	2	1		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	490	201	289		
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	88	38	50		
* X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	200	120	80		
* X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	40	40			
X0325862	CONCRETE BRIDGE RAILING	FOOT	200			200	
X0712400	TEMPORARY PAVEMENT	SQ YD	3,737	2,175	1,562		
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	23	12	11		
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	4	2	2		
X4023000	TEMPORARY ACCESS (ROAD)	EACH	4	2	2		
X6050700	REMOVE INLET BOX	EACH	2	2			
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1	1			
XX003668	PRECONSTRUCTION VIDEO TAPING	L SUM	1	1			
* B2000122	TREE, ACER TATARICUM (TATARIAN MAPLE), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2			
* XX006257	RECESSED REFLECTIVE PAVMENT MARKER	EACH	37	25	12		
XX006646	TREATMENT STRUCTURES	EACH	2	2			
XX006852	EXPLORATION TRENCH (SPECIAL)	CU YD	64	40	24		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	8,333	4,055	4,278		
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2			
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2			
Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHOLES (HOT MIX)	TON	5	3	2		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
Z0019600	DUST CONTROL WATERING	UNIT	25	15	10		
Z0022800	FENCE REMOVAL	FOOT	221	221			
Z0066400	STABILIZED DRIVEWAYS 6"	SQ YD	1,240	721	519		
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1			1	
△ Z0076600	TRAINEES	HOUR	500	500			

△ Y030

• SPECIALTY ITEM

FILE NAME = g:\CH04\0883\Road\Site\184-Sum01.qxd	USER NAME = CECComr	DESIGNED - CEC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ALDEN ROAD SUMMARY OF QUANTITIES	F.A.S. RTE. 0026	SECTION 02-00269-00-BR	COUNTY MCHENRY	TOTAL SHEETS 153	SHEET NO. 8
PLOT SCALE = 50.0000 Ft / IN.	CHECKED - DWB	REVISED -	SHEET NO. 5 OF 5 SHEETS			STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			
PLOT DATE = 8/27/2009	DATE - 08/25/2009	REVISED -								
CONTRACT NO. 63212										