

SUMMARY OF QUANTITIES

SI	CODE NO.	ITEM	UNIT	QUANTITY	80% FED / 20% LOCAL	
					RURAL ROADWAY	BRIDGE STR NO. 056-3177
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	62	62	
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	36	36	
	20200100	EARTH EXCAVATION	CU YD	500	500	
	20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	12	12	
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	161	161	
	20300100	CHANNEL EXCAVATION	CU YD	47	47	
	20400800	FURNISHED EXCAVATION	CU YD	504	504	
	20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	135.8		135.8
	20800150	TRENCH BACKFILL	CU YD	40.5	40.5	
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	237	237	
*	21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	845	845	
*	25000312	SEEDING, CLASS 4A	ACRE	0.11	0.11	
*	25000314	SEEDING, CLASS 4B	ACRE	0.13	0.13	
*	25100630	EROSION CONTROL BLANKET	SQ YD	843	843	
*	25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	845	845	
*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	589	589	
	28000310	AGGREGATE DITCH CHECKS	EACH	1	1	
	28000500	INLET AND PIPE PROTECTION	EACH	8	8	
	28001000	AGGREGATE (EROSION CONTROL)	TON	1.1	1.1	
	28100105	STONE RIPRAP, CLASS A3	SQ YD	13	13	
	28100107	STONE RIPRAP, CLASS A4	SQ YD	320		320
	28200200	FILTER FABRIC	SQ YD	320		320
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	237	237	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	252	252	
	40600300	AGGREGATE (PRIME COAT)	TON	0.8	0.8	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	30	30	
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	65	65	
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N70	TON	83	83	
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	132	132	
	44000100	PAVEMENT REMOVAL	SQ YD	379	379	
	44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	403	403	
	44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	398	398	
	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	240	240	
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	237	237	
	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1

* DENOTES SPECIALTY ITEMS

FILE NAME = p:\p60095873\9002.cad\981.d\evruga\sheet\general\DI60095873-sh-t-5001.dgn

AECOM

USER NAME = pmsarno
 PLOT SCALE = 50.00' / IN.
 PLOT DATE = 5/28/2009

DESIGNED - NJH
 DRAWN - NJH
 CHECKED - RMG
 DATE - MARCH 20, 2009

REVISED -
 REVISED -
 REVISED -
 REVISED -

**MCHENRY COUNTY
 DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0031	06-00323-00-BR	MCHENRY	53	4
CONTRACT NO. 63218				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				