

SUMMARY OF QUANTITIES CONT.

				80% FED / 20% LOCAL	
				RURAL ROADWAY	BRIDGE STR NO. 056-3177
50200100	STRUCTURE EXCAVATION	CU YD	271.4		271.4
50300225	CONCRETE STRUCTURES	CU YD	103.3		103.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	334.8		334.8
50300280	BRIDGE DECK GROOVING	SQ YD	772		772
50300280	CONCRETE ENCASEMENT	CU YD	13.1		13.1
50300300	PROTECTIVE COAT	SQ YD	950		950
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	843		843
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	91,120		91,120
50800515	BAR SPLICERS	EACH	84		84
51201800	FURNISHING STEEL PILES HP14X73	FOOT	756		756
51201900	FURNISHING STEEL PILES HP14X89	FOOT	619		619
51202305	DRIVING PILES	FOOT	1,281		1,281
51203800	TEST PILE STEEL HP14X73	EACH	2		2
51203900	TEST PILE STEEL HP14X89	EACH	1		1
51204650	PILE SHOES	EACH	24		24
51500100	NAME PLATES	EACH	1		1
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4	
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	460	460	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	85		85
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	120		120
60208210	CATCH BASINS, TYPE C, TYPE 20 FRAME AND GRATE	EACH	4	4	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4	
60600605	CONCRETE CURB, TYPE B	FOOT	20	20	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	102	102	
64200105	SHOULDER RUMBLE STRIP	FOOT	423	423	
66500105	WOVEN WIRE FENCE, 4'	FOOT	270	270	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	9	9	
67100100	MOBILIZATION	L SUM	1	1	
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	4	4	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	841	841	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	412	412	

* DENOTES SPECIALTY ITEMS

FILE NAME = p:\a600018873\9800_cad\981_dr\orig\sheet\general\1600018873-sh.t-5002.dgn

AECOM

USER NAME = pmsarino
 PLOT SCALE = 50.000000' / IN.
 PLOT DATE = 5/28/2009

DESIGNED - NJH
 DRAWN - NJH
 CHECKED - RMC
 DATE - MARCH 20, 2009

REVISED -
 REVISED -
 REVISED -
 REVISED -

**MCHENRY COUNTY
 DIVISION OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0031	06-00323-00-BR	MCHENRY	53	5
CONTRACT NO. 63218				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				