

SUMMARY OF QUANTITIES				SIDEWALKS	SIGNALS	
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION	TYPE CODE
					SFTY-1B	YO31-F
	20100110	TREE REMOVAL (6 TO 15 UNIT DIAMETER)	UNITS	95	95	
	20100210	TREE REMOVAL (OVER 15 UNIT DIAMETER)	UNITS	94	94	
*	20101300	TREE PRUNNING (1 TO 10 INCH DIAMETER)	EACH	10	10	
*	20101350	TREE PRUNNING (OVER 10 INCH DIAMETER)	EACH	6	6	
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B, 4 INCH	SQ YD	8554	8554	
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	486	486	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	42602	42602	
	42400410	PORTLAND CEMENT CONCRETE SIDEWALK, 8 INCH	SQ FT	6710	6710	
	42400800	DETECTABLE WARNING	SQ FT	344	344	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2909	2909	
	44000300	CURB REMOVAL	FOOT	151	151	
	44000600	SIDEWALK REMOVAL	SQ FT	1815	1815	
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	724	724	
	542D0211	PIPE CULVERT, CLASS D, TYPE 1, 6 INCH	FOOT	12	12	
*	56400500	FIRE HYDRANT TO BE REMOVED	EACH	6	6	
*	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	6	6	
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1	
	60255500	MANHOLES TO BE ADJUSTED	EACH	7	7	
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1	
	60600605	CONCRETE CURB, TYPE B	FOOT	112	112	
	63200310	GUARDRAIL REMOVAL	FOOT	7.5	7.5	
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	MONTH	6	6	
	67100100	MOBILIZATION	L. SUM	1	1	
	70102635	TRAFFIC CONTROL AND PROTECTION STANDARD 701701	L. SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION STANDARD 701801	L. SUM	1	1	
	72000100	SIGN PANEL, TYPE 1	SQ FT	9	9	
	72400500	REMOVE SIGN PANEL ASSEMBLY, TYPE A	EACH	1	1	
	73000100	WOOD SIGN SUPPORT	FOOT	14	14	
*	78000400	THERMOPLASTIC PAVEMENT MARKING LINE 6 INCH	FOOT	1436	1436	
*	78000600	THERMOPLASTIC PAVEMENT MARKING LINE 12 INCH	FOOT	1174	1174	
*	81400115	HANDHOLE TO BE ADJUSTED	EACH	3	3	
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	599		599
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	652		652
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4		4
*	88102748	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1		1
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	4		4
*	88600100	DETECTOR LOOP, TYPE I	FOOT	103		103
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	5		5
*	89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1		1
*	89502200	MODIFY EXISTING CONTROLLER	EACH	1		1
*	X0912300	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	LSUM	1		1
*	A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	11	11	
*	X0322256	TEMPORARY INFORMATION SIGHNING	SQ FT	206	206	
*	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1		1
*	X8780110	MODIFY EXISTING TYPE "D" FOUNDATION	EACH	1		1
	Z0022800	FENCE REMOVAL	FOOT	18	18	
△	Z0076600	TRAINEES	hour	500	500	
*	XX006425	RESTORATION	SQ YD	2609	2609	
	XX008198	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 11 3/4 INCH	SQ YD	2887	2887	
	XX007278	PARKWAY RESTORATION	SQ YD	476	476	
	X0326472	HOT-MIX ASPHALT REMOVAL	SQ YD	114	114	
	XX008199	HOT-MIX ASPHALT PARKWAY, 5 INCH	SQ YD	97	97	
*	K0026840	SHRUBS TO BE RELOCATED	EACH	6	6	

△ Y080

\* - INDICATES SPECIALTY ITEMS

FILE NAME = 08291-QUAN-01 - IDOT P01	USER NAME =	DESIGNED -- RJW	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SIDEWALK IMPROVEMENTS SUMMARY OF QUANTITIES			F.A.U. RTE. 2757/1537	SECTION 09-00060-00-SW	COUNTY COOK	TOTAL SHEETS 35	SHEET NO. 3
	PLOT SCALE =	CHECKED -- RJW	REVISED --					CONTRACT NO. 63228				
	PLOT DATE = 08-20-09	DRAWN -- PS	REVISED --									
		CHECKED -- AG	REVISED --					FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(325)				