

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE						
					1000-2A	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031-1F	Y080
	70300280	TEMPORARY PAVEMENT MARKING—LINE 24"	FOOT	200	200						
	72000100	SIGN PANEL - TYPE 1	SQ FT	28.5	28.5						
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	191	191						
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4300	4300						
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1560	1560						
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	81	81						
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	147	147						
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	95	95						
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	275	275						
*	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	506						506	
*	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	224				145		79	
*	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	16						16	
*	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	36						36	
*	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	276						276	
*	81400100	HANDHOLE	EACH	6						6	
*	81400200	HEAVY-DUTY HANDHOLE	EACH	3						3	
*	81400300	DOUBLE HANDHOLE	EACH	1						1	
*	81603172	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.8 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	720				720			
*	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1321				720		601	
*	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	2				2			
*	82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4				4			
*	83008400	LIGHT POLE, ALUMINUM, 40 FT. M.H., 10 FT. MAST ARM	EACH	2				2			
*	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	50				50			
*	83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	10				10			
*	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	5				5			
*	84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	1				1			
*	84200705	LIGHTING FOUNDATION REMOVAL, PARTIAL	EACH	3				3			
*	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3				3			
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1						1	
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	573						573	
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1304						1304	
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1220						1220	
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1509						1509	
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1774						1774	
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4						4	
*	87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1						1	
*	87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	2						2	
*	87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1						1	
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16						16	
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	54						54	
*	87900200	DRILL EXISTING HANDHOLE	EACH	3						3	
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	7						7	
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4						4	
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4						4	
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2						2	
*	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2						2	
*	88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	11						11	
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	5						5	
*	88600100	DETECTOR LOOP, TYPE I	FOOT	936						936	

\* - INDICATES SPECIALTY ITEMS

FILE NAME = 06959-QUAN-01 - P02	USER NAME =	DESIGNED -- MRS	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US ROUTE 6 (162ND STREET) & WAUSAU AVENUE INTERSECTION IMPROVEMENTS SUMMARY OF QUANTITIES			F.A.P. RTE. 351	SECTION 09-00086-00-CH	COUNTY COOK	TOTAL SHEETS 43	SHEET NO. 4
	PLOT SCALE =	CHECKED -- PKB	REVISED --		SCALE:	SHEET NO. 4	OF 43 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT M-9003(330)
	PLOT DATE = 9-3-09	DRAWN -- PS	REVISED --		CONTRACT NO. 63261							
		CHECKED -- AG	REVISED --									