

| SUMMARY OF QUANTITIES | | | | | PAVEMENT | MARKINGS | SIGNS | LANDSCAPE | LIGHTS | SIGNALS | TRAINING |
|-----------------------|----------|---|-------|-------|------------------------|----------|---------|-----------|---------|---------|----------|
| S.I. | CODE NO. | PAY ITEM | UNIT | QUAN | CONSTRUCTION TYPE CODE | | | | | | |
| | | | | | I000 | SFTY-1D | Y002-1C | Y003 | Y030-1E | Y031 | Y080 |
| * | 88700200 | LIGHT DETECTOR | EACH | 2 | | | | | | 2 | |
| * | 88800100 | PEDESTRIAN PUSH-BUTTON | EACH | 4 | | | | | | 4 | |
| * | 89000100 | TEMPORARY TRAFFIC SIGNAL INSTALLATION | EACH | 1 | | | | | | 1 | |
| * | 89501400 | RELOCATE EXISTING <i>EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT</i> | EACH | 1 | | | | | | 1 | |
| * | 89502210 | MODIFY EXISTING CONTROLLER CABINET | EACH | 1 | | | | | | 1 | |
| * | 89502300 | REMOVE ELECTRIC CABLE FROM CONDUIT | FOOT | 13717 | | | | | | 13717 | |
| * | 89502350 | REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT | FOOT | 4000 | | | | | | 4000 | |
| * | 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT | EACH | 1 | | | | | | 1 | |
| * | 89502380 | REMOVE EXISTING HANDHOLE | EACH | 7 | | | | | | 7 | |
| * | 89502385 | REMOVE EXISTING CONCRETE FOUNDATION | EACH | 6 | | | | | | 6 | |
| * | B2005720 | TREE, PYRUS CALLERYANA CHANTICLEER CHANTICLEER CALLERY PEAR), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED | EACH | 11 | 11 | | | | | | |
| | X0322923 | SEGMENTAL CONCRETE BLOCK WALL | SQ FT | 2667 | 2667 | | | | | | |
| * | X0322925 | ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C | FOOT | 6000 | | | | | | 6000 | |
| | X0323350 | FURNISHING AND SETTING BRICK PAVERS | SQ FT | 1455 | 1455 | | | | | | |
| * | X0325890 | RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1 | EACH | 1 | | | | | | 1 | |
| * | X8620020 | UNINTERRUPTIBLE POWER SUPPLY | EACH | 1 | | | | | | 1 | |
| * | X8710022 | FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 2-MM12F & SM12F | FOOT | 6000 | | | | | | 6000 | |
| * | X8730027 | ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C | FOOT | 532 | | | | | | 532 | |
| * | X8730250 | ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED | FOOT | 302 | | | | | | 302 | |
| * | X8950200 | REBUILD EXISTING HANDHOLE | EACH | 1 | | | | | 1 | | |
| * | XX000679 | CUT AND CAP EXISTING WATER MAIN | EACH | 2 | 2 | | | | | | |
| | XX001186 | PLANTER REMOVAL | EACH | 1 | 1 | | | | | | |
| | XX006806 | HOT MIX ASPHALT DRIVEWAY PAVEMENT | SQ YD | 281 | 281 | | | | | | |
| * | XX006937 | GROUND ROD, 5/8" DIA. X 10 FT. | EACH | 6 | | | | | 6 | | |
| | Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1 | 1 | | | | | | |
| | Z0076600 | TRAINEES | HOURL | 500 | | | | | | | 500 |
| * | XX008193 | 12" X 12" TAPPING SLEEVE AND 12" VALVE IN 5' DIA VALVE VAULT, TYPE A | EACH | 1 | 1 | | | | | | |
| * | XX008194 | 24 INCH DIAMETER STEEL SLEEVE, 0.375 INCH WALL THICKNESS, OPEN CUT | FOOT | 31 | 31 | | | | | | |
| | XX00717 | <i>STORM SEWER CONNECTION, SPECIAL</i> | EACH | 2 | 2 | | | | | | |
| * | XX003037 | DUCTILE IRON FITTINGS AND ACCESSORIES | POUND | 1086 | 1086 | | | | | | |
| * | XX007672 | DUCTILE IRON WATER MAIN 6" POLYETHYLENE WRAPPED | FOOT | 15 | 15 | | | | | | |
| * | XX007673 | DUCTILE IRON WATER MAIN 12" POLYETHYLENE WRAPPED | FOOT | 266 | 266 | | | | | | |
| | XX008195 | EXPLORATION EXCAVATION, (UTILITY). | FOOT | 100 | 100 | | | | | | |
| * | 56400200 | FIRE HYDRANTS <i>TO BE MOVED (SPECIAL)</i> | EACH | 1 | 1 | | | | | | |
| * | XX004760 | FIRE HYDRANT WITH AUXILIARY VALVE, VALVE BOX AND TEE | EACH | 1 | 1 | | | | | | |
| * | XX004972 | LINESTOP, 12" | EACH | 1 | 1 | | | | | | |
| * | XX008196 | TRENCH BACKFILL, WATERMAIN (SPECIAL) | FOOT | 281 | 281 | | | | | | |

* - INDICATES SPECIALTY ITEMS

| | | | | | | | | | | |
|---------------------------------|----------------|-----------------|--------------------|---|---|--------------------------|--------------|-----------------------|--------------|------------------------------|
| FILE NAME = 08859-QUAN-01 - P03 | USER NAME = | DESIGNED -- MRS | REVISED -- | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | US ROUTE 6 (162ND STREET) & WAUSAU AVENUE INTERSECTION IMPROVEMENTS SUMMARY OF QUANTITIES | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | CHECKED -- PKB | REVISED -- | 351 | | | 09-00086-00-CH | COOK | 43 | 5 | |
| PLOT SCALE = | DRAWN -- PS | REVISED -- | CONTRACT NO. 63261 | | | | | | | |
| PLOT DATE = 9-3-09 | CHECKED -- AG | REVISED -- | SCALE: | | | SHEET NO. 5 OF 43 SHEETS | STA. TO STA. | FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT M-9003(330) |