

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION CODE	
					I000	SFTY-1D
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	26	26	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2377	2377	
	40600300	AGGREGATE (PRIME COAT)	TON	36	36	
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	535	535	
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3	3	
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2000	2000	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	868	868	
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	23772	23772	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	62	62	
	44000600	SIDEWALK REMOVAL	SQ FT	716	716	
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300	
	44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	200	200	
	44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	100	100	
	60255500	MANHOLES TO BE ADJUSTED	EACH	14	14	
	60260100	INLETS TO BE ADJUSTED	EACH	10	10	
	67100100	MOBILIZATION	L SUM	1	1	
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3150		3150
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	438		438
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182		182
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11472		11472
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	850		850
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120		120
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	90		90
*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	220		220
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	371		371
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1000	1000	

\* - INDICATES SPECIALTY ITEMS

**GENERAL NOTES:**

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- THE NOMINAL THICKNESS OF HOT-MIX ASPHALT MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HOT-MIX ASPHALT SURFACE IS PLACED.
- CHANGEABLE MESSAGE SIGNS SHALL BE ERECTED AT LEAST 10 DAYS PRIOR TO START OF CONSTRUCTION.

FILE NAME = 09275-QUAN-01 - 001

USER NAME =	DESIGNED -- JRD	REVISED --
	CHECKED -- HLG	REVISED --
PLOT SCALE =	DRAWN -- LTL	REVISED --
PLOT DATE = 08-07-09	CHECKED -- HLG	REVISED --

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

135TH STREET RESURFACING IL-53 TO SANITARY & SHIP CANAL BRIDGE SUMMARY OF QUANTITIES			
SCALE: NONE	SHEET NO. 2 OF 11 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0282	09-00053-00-RS	WILL	11	2
CONTRACT NO. 63264			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003-(361)	