

P. A. P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	09-00059-00-CH	COOK	046	003
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT ARA-9003(340)	

CONTRACT #63269

SUMMARY OF QUANTITIES					PAVEMENT	LIGHTING
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE	
					J000-2A	Y030-1E
	20200100	EARTH EXCAVATION	CU YD	3765	3765	
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	790	790	
	20800150	TRENCH BACKFILL	CU YD	141	141	
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1675	1675	
	21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	845	845	
	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	200		200
	25000210	SEEDING, CLASS 2A	ACRE	0.5	0.5	
	25000400	NITROGEN NUTRIENT	POUND	45	45	
	25000500	PHOSPHORUS NUTRIENT	POUND	45	45	
	25000600	POTASSIUM NUTRIENT	POUND	45	45	
	25100630	EROSION CONTROL BLANKET	SQ YD	2600	2600	
	28000400	PERIMETER EROSION BARRIER	FOOT	1000	1000	
	28000510	INLET FILTERS	EACH	18	18	
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	4603	4603	
	31200100	STABILIZED SUB-BASE 4"	SQ YD	4603	4603	
	42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	3756	3756	
	42001200	PAVEMENT FABRIC	SQ YD	3756	3756	
	42001300	PROTECTIVE COAT	SQ YD	4862	4862	
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVMENT, 8 INCH	SQ YD	62	62	
	44000100	PAVEMENT REMOVAL	SQ YD	138	138	
	44000200	DRIVEWAY PAVMENT REMOVAL	SQ YD	232	232	
	44000300	CURB REMOVAL	FOOT	127	127	
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FT	2974	2974	
	550A0050	STORM SEWER, CLASS A, TYPE 1, 12"	FOOT	116	116	
	550A0320	STORM SEWER, CLASS A, TYPE 2, 8"	FOOT	4	4	
	550A0330	STORM SEWER, CLASS A, TYPE 2, 10"	FOOT	10	10	
	550A0340	STORM SEWER, CLASS A, TYPE 2, 12"	FOOT	417	417	
	55100500	STORM SEWER REMOVAL, 12"	FOOT	158	158	
*	56400500	FIRE HYDRANT TO BE REMOVED	EACH	1	1	
*	56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1	1	
	60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	3	3	
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	11	11	
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	3	3	
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1	
	60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1	
	60251730	CATCH BASIN TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	1	1	
	60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1	
	60255500	MANHOLES TO BE ADJUSTED	EACH	4	4	
	60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1	
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1	
	60500050	REMOVING CATCH BASINS	EACH	6	6	
	60500205	FILLING CATCH BASINS	EACH	1	1	
	60500705	CATCH BASINS TO BE FILLED TO MAINTAIN FLOW	EACH	5	5	
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	1.5	1.5	
	60600605	CONCRETE CURB, TYPE B	FOOT	55	55	
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE-B6.12	FOOT	831	831	
	60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE-B6.12, (SPECIAL)	FOOT	40	40	
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE-B6.24	FOOT	2550	2550	
	67100100	MOBILIZATION	L. SUM	1	1	

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP 348 (HARLEM AVENUE)
DRIVEWAY RECONFIGURATION
SUMMARY OF QUANTITIES

SCALE: VERT. NA
HORIZ. NA
DATE 08-14-09

DRAWN BY PS
CHECKED BY RJW