

F. A. P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	09-00059-00-CH	COOK	046	004
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	ARA-9003(340)	

CONTRACT #63269

SUMMARY OF QUANTITIES					PAVEMENT	LIGHTING	
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE		
					J000-2A	Y030-1E	
	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L. SUM	1	1		
	72000100	SIGN PANEL, TYPE 1	SQ FT	53	53		
	72000200	SIGN PANEL, TYPE 2	SQ FT	12	12		
	73000100	WOOD SIGN SUPPORT	FOOT	154	154		
*	78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- LETTERS AND SYMBOLS	SQ FT	110	110		
*	78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- LINE 4"	FOOT	379	379		
*	78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- LINE 6"	FOOT	1416	1416		
*	78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B- LINE 8"	FOOT	619	619		
*	78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	255	255		
*	78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	90	90		
	81018500	CONDUIT PUSHED, 2" DIA GALVANIZED STEEL	FOOT	260		260	
	81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	575		575	
	81400100	HANDHOLE	EACH	1		1	
	81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	2925		2925	
	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2250		2250	
	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	80		80	
	83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	10		10	
	83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	9		9	
	84200700	LIGHTING FOUNDATION REMOVAL	EACH	9		9	
	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	9		9	
	88600100	DETECTOR LOOP, TYPE 1	FOOT	90		90	
	87900200	DRILL EXISTING HANDHOLE	EACH	1		1	
	89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	260		260	
	89502380	REMOVING EXISTING HANDHOLE	EACH	1		1	
	X0322256	TEMPORARY INFORMATION SIGNS	SQ FT	52	52		
	XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	9		9	
	Z0022800	FENCE REMOVAL	FOOT	625	625		
	XX008191	REPLACE DAMAGED LUMINAIRE, HPS, 400 WATT	EACH	2		2	
	83050810	REPLACE DAMAGED LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	2		2	
*	XX007907	STAMPED CONCRETE MEDIAN SURFACE, 5"	SQ FT	382	382		
*	XX007908	COLORED SURFACE	SQ FT	382	382		

* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP 348 (HARLEM AVENUE)
DRIVEWAY RECONFIGURATION
SUMMARY OF QUANTITIES

SCALE: VERT. NA
HORIZ. NA
DATE: 08-14-09

DRAWN BY PS
CHECKED BY RJW