

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY	ROADWAY
				100%FEDERAL NORTH OAK AVENUE 1000	100%FEDERAL WEST BARTLETT ROAD 1000
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	62	62	
20101100	TREE TRUNK PROTECTION	EACH	71	71	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1449	1449	
20400800	FURNISHED EXCAVATION	CU YD	51	51	
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	81	81	
20800150	TRENCH BACKFILL	CU YD	450	450	
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6055	6055	
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	50	50	
21400100	GRADING AND SHAPING DITCHES	FOOT	1250	1250	
* 25200650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	6051	6051	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUNDS	125	125	
28000510	INLET FILTERS	EACH	29	29	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2863	2863	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	300	300	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	3630	1585	2045
40600300	AGGREGATE (PRIME COAT)	TON	80	35	45
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1764		1764
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	329	214	115
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1740	1740	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3185	1127	2058
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	2420	2420	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	375	375	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	14448	14448	
42400800	DETECTABLE WARNINGS	SQ FT	100	100	
44000100	PAVEMENT REMOVAL	SQ YD	2077	2077	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	20445		20445
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	13063	13063	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1050	1050	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	695	695	
44000600	SIDEWALK REMOVAL	SQ FT	12,505	12,505	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	735	145	590
44004250	PAVED SHOULDER REMOVAL	SQ YD	285	285	
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	146	105	41
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	582	418	164
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	582	418	164
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	146	105	41
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	420	420	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	85	85	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	440	440	
55100700	STORM SEWER REMOVAL 15"	FOOT	290	290	
550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	344	344	
550A0360	STORM SEWERS, CLASS A, TYPE 2, 15"	FOOT	841	841	
* 56300300	ADJUSTING WATER SERVICE LINES	FOOT	52	52	
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1	
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2	
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	10	10	
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	5	5	
60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	4	4	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5	

PAYCODE	ITEM DESCRIPTION	UNIT	TOTAL	ROADWAY	ROADWAY
				100%FEDERAL NORTH OAK AVENUE 1000	100%FEDERAL WEST BARTLETT ROAD 1000
60222000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	1	
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	2	2	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	14	14	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	21	16	5
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5	5	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	3750	3,750	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	520	90	430
70300200	TEMPORARY PAVEMENT MARKING	FOOT	7980	7980	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2130	2018	112
72000100	SIGN PANEL - TYPE 1	SQ FT	30	30	
72000200	SIGN PANEL - TYPE 2	SQ FT	20	20	
72900200	METAL POST - TYPE B	FOOT	100	100	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	545	91	454
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16,610	3070	13,540
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1150	50	1100
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1805	910	895
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	190	190	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	210		210
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	210		210
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	154	154	
* A2001224	TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	3	3	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	110	55	55
X4023000	TEMPORARY ACCESS (ROAD)	EACH	1	1	
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1	
XX005565	REMOVE AND RESET BRICK PAVERS	SQ FT	50	50	
XX007490	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SQ YD	705	705	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	12	12	
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	2	2	
Δ Z0076600	TRAINEES	HOURS	500	500	

* SPECIALTY ITEM
Δ Y080

COMPANY NAME: SEC GROUP, INC.
PROJECT CONTACT: J. MELNICH
CLIENT: VILLAGE OF BARTLETT
DATE PLOTTED: 8/31/2009 4:55:28 PM
FILE NAME: 090196-summary.dgn
PLOT SCALE: PEN TABLE:
SOURCE: c:\frans.tbl



USER NAME = jmelnich	DESIGNED - J. ATTANASEO	REVISED -
FILE NAME = 090196-summary.dgn	DRAWN -	REVISED -
PLOT SCALE = N.T.S.	CHECKED - T. HAMILTON	REVISED -
PLOT DATE = 8/31/2009	DATE - 8/3/09	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. OF SHEET STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2537	09-00084-00-RS	COOK	53	3
CONTRACT NO.				63274
FED. ROAD DIST. NO. IL'INDIS FED. AID PROJECT ARA-9003 (345)				