SUMMARY OF QUANTITIES

	CODE NO.	ITEMS	UNIT	QUANTITY (1000)
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,650
	40600300	AGGREGATE (PRIME COAT)	TON	108
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2,985
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	43
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,612
	44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	26,648
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	270
	44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	200
	44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	200
	44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	200
	44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	200
	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	100
	67100100	MOBILIZATION	L SUM	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	556
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	551
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18,868
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,517
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,549
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	236
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11,306
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	551
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18,868
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,517
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,549
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	236
*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	504

* - SPECIALTY ITEM

FILE NAME = $FILES PLOT DATE = 8/20/2009 $TIMES	DESIGNED - / DRAWN - / CHECKED - / DATE -	REVISED - / REVISED - / REVISED - / REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GREEN BAY ROAD RESURFACING SUMMARY OF QUANTITIES	SCALE : N/A	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2744	09-00062-00-RS	COOK	16	3
		CONTRACT NO. 63278		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		