

SUMMARY OF QUANTITIES

DATE	
BY	
PLAN	
NOTE BOOK NO.	
SUBMITTED	
PLOTTED	
CHECKED	
BY	
DATE	

DATE	
BY	
PROFILE	
NOTE BOOK NO.	
SUBMITTED	
PLOTTED	
CHECKED	
BY	
DATE	

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY SFTY-1B
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	66	66
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	61	61
20101000	TEMPORARY FENCE	FOOT	760	760
^ 20101200	TREE ROOT PRUNING	EACH	44	44
^ 20101300	TREE PRUNING (1 to 10 INCH DIAMETER)	EACH	14	14
^ 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	11	11
20200100	EARTH EXCAVATION	CUYD	558	558
20800150	TRENCH BACKFILL	CUYD	40	40
* ^ 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQYD	2940	2940
* 21300010	EXPLORATION TRENCH, SPECIAL	FOOT	20	20
^ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	37	37
^ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	37	37
^ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	37	37
^ 25200110	SODDING, SALT TOLERANT	SQYD	2940	2940
25200200	SUPPLEMENTAL WATERING	UNIT	36	36
28000400	PERIMETER EROSION BARRIER	FOOT	200	200
28000510	INLET FILTERS	EACH	21	21
42001300	PROTECTIVE COAT	SQYD	1464	1464
* 42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQYD	85	85
* 42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQFT	12350	12350
42400800	DETECTABLE WARNINGS	SQFT	147	147
* 44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	670	670
44000600	SIDEWALK REMOVAL	SQFT	41	41
* 44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQYD	50	50
550A0030	STORM SEWERS, CLASS A, TYPE 1 8"	FOOT	312	312
550A0040	STORM SEWERS, CLASS A, TYPE 1 10"	FOOT	3	3
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	35	35

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY SFTY-1B
* 55039700	STORM SEWERS TO BE CLEANED	FOOT	200	200
55100200	STORM SEWER REMOVAL 6"	FOOT	7	7
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	3	3
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	2	2
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	3	3
67100100	MOBILIZATION	L. SUM	1	1
* 70101700	TRAFFIC CONTROL AND PROTECTION	L. SUM	1	1
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	24	24
^ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	432	432
^ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	113	113
78300100	PAVEMENT MARKING REMOVAL	SQFT	283	283
* Z0017400	DRAINAGE & UTILITY STRUCTURE TO BE ADJUSTED	EACH	5	5
* Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4
* Z0077700	WOOD FENCE TO BE REMOVED AND RE-ERECTED	FOOT	15	15
* LR430030	CONCRETE PAVER PAVEMENT	SQYD	254	254
* X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	22	22
* XX003668	PRECONSTRUCTION VIDEO TAPING	L. SUM	1	1
* XX004653	CURB SAW CUT	FOOT	25	25
* XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQYD	128	128
^ A2005620	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5
^ A2005824	TREE, PLATANUS OCCIDENTALIS (SYCAMORE), 3" CALIPER, BALLED AND BURLAPPED	EACH	5	5
^ A2007624	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 3" CALIPER, BALLED AND BURLAPPED	EACH	5	5
^ B2006220	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5
*	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 8"	FOOT	11	11

^ DENOTES SPECIALTY ITEM
 * DENOTES SPECIAL PROVISION

FILE NAME =	USER NAME =	DESIGNED SJC	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DEE ROAD SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN SJC	REVISED --				08-00144-00-SW	COOK	15	3	
		CHECKED JRV	REVISED --			SHEET NO. 3 OF 15 SHEETS STA. TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS		CONTRACT NO. 63279	
		DATE 08/12/2009	REVISED --					FED. AID PROJECT			