# SUMMARY OF QUANTITIES

| | CODE NO | ITEMS | UNIT | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | |
|---|---|---|---|---|---|---|
| | | | | | 80% FED URBAN I000 | 20% LOCAL URBAN I000 |
| | 20101300 | Tree Pruning (1 to 10 Inch Diameter) | EACH | 6.00 | 5.00 | 1.00 |
| | 20101350 | Tree Pruning (Over 10 Inch Diameter) | EACH | 43.00 | 34.00 | 9.00 |
| | 20101700 | Supplemental Watering | UNIT | 30.00 | 24.00 | 6.00 |
| * | 25200700 | Sodding, Special | SQYD | 500.00 | 400.00 | 100.00 |
| | 40201000 | Aggregate for Temporary Access | TON | 140.00 | 112.00 | 28.00 |
| | 40300100 | Bituminous Materials (prime coat) | GAL | 5,300.00 | 4,240.00 | 1,060.00 |
| | 40600300 | Aggregate (prime coat) | TON | 50.00 | 40.00 | 10.00 |
| | 40600400 | Mixture for Cracks, Joints and Flangeways | TON | 20.00 | 16.00 | 4.00 |
| | 40600635 | Leveling Binder (Machine Method), N70 | TON | 1,736.00 | 1,359.00 | 347.00 |
| | 40600895 | Constructing Test Strip | EACH | 1.00 | 0.80 | 0.20 |
| | 40600982 | Hot-Mix Asphalt Surface Removal - Butt Joint | SQYD | 390.00 | 312.00 | 78.00 |
| | 40603310 | Hot-Mix Asphalt Surface Course, Mix "C", N50 | TON | 50.00 | 40.00 | 10.00 |
| | 40603340 | Hot-Mix Asphalt Surface Course, Mix "D", N70 | TON | 2,604.00 | 2,083.00 | 521.00 |
| | 42300300 | Portland Cement Concrete Driveway Pavement, 7 Inch | SQYD | 1,450.00 | 1,160.00 | 290.00 |
| | 44000159 | Hot-Mix Asphalt Surface Removal, 2 ½" | SQYD | 31,000.00 | 24,800.00 | 6,200.00 |
| | 44000200 | Driveway Pavement Removal | SQYD | 1,900.00 | 780.00 | 380.00 |
| | 44001700 | Combination Concrete Curb and Gutter Removal and Replacement | FOOT | 11,500.00 | 9,200.00 | 2,300.00 |
| | 44004610 | Sidewalk Removal and Replacement | SQFT | 8,400.00 | 6,720.00 | 1,680.00 |
| △ | 56500600 | Domestic Water Service Box to be Adjusted | EACH | 36.00 | 29.00 | 7.00 |
| | 60234200 | Inlets, Type A, Type 1 Frame, Open Lid | EACH | 1.00 | 0.80 | 0.20 |
| | 60260100 | Inlets to be Adjusted | EACH | 29.00 | 23.00 | 6.00 |
| | 60266100 | Valve Vaults to be Reconstructed | EACH | 1.00 | 0.80 | 0.20 |
| | 60300305 | Frames and Lids to be Adjusted | EACH | 7.00 | 6.00 | 1.00 |
| * | 60300310 | Frames and Lids to be Adjusted (Special) | EACH | 76.00 | 61.00 | 15.00 |
| | 60406000 | Frames and Lids, Type 1, Open Lid | EACH | 3.00 | 2.00 | 1.00 |
| | 60406100 | Frames and Lids, Type 1, Closed Lid | EACH | 44.00 | 35.00 | 9.00 |
| | 67100100 | Mobilization | LSUM | 1.00 | 0.80 | 0.20 |
| | 70102625 | Traffic Control and Protection, Standard 701606 | LSUM | 1.00 | 0.80 | 0.20 |
| | 70102632 | Traffic Control and Protection, Standard 701602 | LSUM | 1.00 | 0.80 | 0.20 |
| | 70102635 | Traffic Control and Protection, Standard 701701 | LSUM | 1.00 | 0.80 | 0.20 |
| | 70102640 | Traffic Control and Protection, Standard 701801 | LSUM | 1.00 | 0.80 | 0.20 |
| △ | 78000100 | Thermoplastic Pavement Marking - Letters and Symbols | SQFT | 72.80 | 58.20 | 14.60 |
| △ | 78000200 | Thermoplastic Pavement Marking Line - 4" | FOOT | 10,896.00 | 8,717.00 | 2,179.00 |
| △ | 78000400 | Thermoplastic Pavement Marking Line - 6" | FOOT | 1,263.00 | 1,010.00 | 253.00 |
| △ | 78000600 | Thermoplastic Pavement Marking Line - 12" | FOOT | 384.00 | 307.00 | 77.00 |
| △ | 78000650 | Thermoplastic Pavement Marking Line - 24" | FOOT | 80.00 | 64.00 | 16.00 |
| * △ | 88600600 | Detector Loop Replacement | FOOT | 184.20 | 184.00 | 0.20 |
| * | XX007729 | Detectable Warnings, Special | SQFT | 672.00 | 538.00 | 134.00 |
| | XX005138 | Class B Patches (Special) | SQYD | 400.00 | 320.00 | 80.00 |

* Indicates Special Provision △ SPECIALTY ITEMS

| FILE NAME = | USER NAME | DESIGNED M.L.ZIEMBA | REVISED | VILLAGE OF SKOKIE | MAIN STREET SKOKIE BLVD. TO CRAWFORD AVE. | F.A.U. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|---|---|---|---|---|---|
| | | DRAWN M.L.ZIEMBA | REVISED | | | 1329 | 09-00282-00-RS | COOK | 17 | 3 |
| | PLOT SCALE | CHECKED E.P.COOK | REVISED | | | | | CONTRACT NO. 63281 | | |
| | PLOT DATE | DATE JUNE 2009 | REVISED | | SCALE: NONE / SHEET NO. 3 OF 17 / STA. # TO STA. # | FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

G:\CADfiles\Engineering\MAIN ST, MISC\SUMMARY OF QUANTITIES_GENERAL NOTES.dwg, 8/21/2009 1:37:36 PM