

SUMMARY OF QUANTITIES

PAY ITEM #	DESCRIPTION	UNIT	Qty.
20101200	TREE ROOT PRUNING	EACH	1.00
20200100	EARTH EXCAVATION	CU YD	2.00
28000510	INLET FILTERS	EACH	49.00
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	40.00
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,217.92
40600300	AGGREGATE (PRIME COAT)	TON	24.36
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,510.00
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	12.00
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	146.30
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3,095.00
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	12,179.22
44000600	SIDEWALK REMOVAL	SQ FT	3,095.00
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,009.50
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	362.10
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	3.00
60260200	INLETS TO BE ADJUSTED, SPECIAL	EACH	15.00
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	21.00
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.00
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	504.00
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	661.00
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	171.00
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	188.00
XX000406	BRICK PAVER REMOVAL AND REPLACEMENT	SQ FT	714.00
XX005833	TREE PROTECTION, SPECIAL	L SUM	1.00
XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	7.20
XX007369	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT, 8"	SQ YD	21.60
XX007729	DETECTABLE WARNINGS, SPECIAL	SQ FT	88.00
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	597.00
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	42.00
XX002258	STRUCTURES TO BE ADJUSTED	EACH	6.00
XX007079	CONCRETE RIBBON	FOOT	204.00
* XX008171	SPRINKLER SYSTEM REPAIR	L SUM	1.00
67100100	MOBILIZATION	L SUM	1.00

*INDICATES SPECIALTY ITEM

FILE NAME = N:\wilmette\VILLAGE LAPP PROJECT\DWG's\quo.dwg	USER NAME = MAGOLDEN	DESIGNED - LMF	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES VILLAGE OF WILMETTE - 10th STREET/WILMETTE AVENUE	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = NTS	CHECKED - LMF	REVISED - ---	1297			09-00186-00-RS	COOK	17	2	
PLCT DATE = 8/21/2009	DATE - 06/25/09	REVISED - ---	CONTRACT NO. 63282							
						NTS	SHEET NO. -- OF --- SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT