

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	1000 TOTAL QUANTITY	1000 100% FEDERAL 0% LOCAL
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	400	400
25000400	NITROGEN FERTILIZER NUTRIENT	FOUND	5	5
25000500	PHOSPHORUS FERTILIZER NUTRIENT	FOUND	5	5
25000600	POTASSIUM FERTILIZER NUTRIENT	FOUND	5	5
25200100	SODDING	SQ YD	400	400
25200200	SUPPLEMENTAL WATERING	UNIT	10	10
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	40	40
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,650	1,650
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	450	450
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,800	1,800
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	10	10
42101300	PROTECTIVE COAT	SQ YD	150	150
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	50	50
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	500	500
⊛ 42400800	DETECTABLE WARNINGS	SQ FT	40	40
⊛ 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	16,500	16,500
⊛ 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50	50
⊛ 44000600	SIDEWALK REMOVAL	SQ FT	500	500
⊛ 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	350	350
⊛ 44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	50	50
⊛ 44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	50	50
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1
⊛ 60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	52	52
⊛ 60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5
⊛ 60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5
67100100	MOBILIZATION	L SUM	1	1
⊛ 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
★ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	85	85
★ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,000	1,000
★ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,000	3,000
★ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100
★ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	400	400
⊛ Z0004900	BITUMINOUS MIXTURE FOR PATCHING POTHOLES (HOT MIX)	TON	20	20
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,000	1,000

- ★ DENOTES SPECIALTY ITEM
- ⊛ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

Drawing File: W:\Projects\600090265 - Division Street LRP Application\Quantities-DivisionS.dwg Aug 13, 2009 - 4:06pm

HANCOCK ENGINEERING
 Civil Engineers
 Municipal Consultants
 Established 1911

USER NAME	DESIGNED	TG	REVISED
	DRAWN	TG/LEV	REVISED
PLOT SCALE	CHECKED	JG	REVISED
PLOT DATE	DATE	08/12/09	REVISED

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1026	09-00113-00-RS	COOK	14	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003(327)			CONTRACT NO. 63290	

E.H.E. PROJECT NO. 600-09-15901