

### SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONST. CODE
			1000
			TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,132
40600300	AGGREGATE (PRIME COAT)	TON	103
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,797
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	237
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,874
Δ 40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	28
Δ 42400800	DETECTABLE WARNINGS	SQ FT	270
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	25,660
Δ 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2,579
Δ 44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	9,328
Δ 44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	75
Δ 44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	61
Δ 44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	2,427
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	19,365
44000600	SIDEWALK REMOVAL	SQ FT	280
Δ 550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	44
Δ 550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	8
Δ 55038000	STORM SEWERS TO BE CLEANED 18"	FOOT	110
Δ 55100500	STORM SEWER REMOVAL 12"	FOOT	44
60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	2
60240312	INLETS, TYPE B, TYPE 11V FRAME AND GRATE	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	1
60260100	INLETS TO BE ADJUSTED	EACH	10

Δ SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEMS

CODE NO.	PAY ITEM	UNIT	CONST. CODE
			1000
			TOTAL QUANTITY
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	2
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1
67100100	MOBILIZATION	L SUM	1
Δ 70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,600
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	35
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12,600
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,100
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	500
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	250
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,200
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	35
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12,600
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,100
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	500
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	250
Δ * 88600600	DETECTOR LOOP REPLACEMENT	FOOT	215
Δ X6028300	INLETS TO BE REMOVED, SPECIAL	EACH	2
Δ XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	9
Δ XX006215	BRICK PAVER REMOVAL AND REPLACEMENT	SQ YD	35
Δ XX006425	RESTORATION	SQ YD	1,256
Δ XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	500
Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1

Δ SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEMS

Plotted: August 14, 2009 @ 11:58 AM By: Kris Pung - Tab: 03 Sum of Quant 2/2/34

COPYRIGHT © 2009 ENGINEERING ENTERPRISES, INC.

**Engineering Enterprises, Inc.**  
CONSULTING ENGINEERS  
52 Wheeler Road  
Sugar Grove, Illinois 60554  
630.466.6700 / www.eeiweb.com

**CITY OF GENEVA**  
KANE COUNTY, ILLINOIS

NO.	DATE	REVISIONS

**KANEVILLE ROAD**  
LAPP IMPROVEMENTS

**SUMMARY OF QUANTITIES**

DATE:	AUGUST 2009
PROJECT NO:	GE0901
FILE:	GE0901-CVR
SHEET	<b>3</b> OF <b>18</b>

Path: H:\SDS\PROJ\GE0901\DWG\DWG\_FINAL\_ENG\GE0901-CVR