

# INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET, LOCATION MAP
2	INDEX OF SHEETS, LEGEND OF SYMBOLS, AND I.D.O.T. STANDARD DRAWINGS
3	GENERAL NOTES
4	SUMMARY OF QUANTITIES
5-6	EXISTING AND PROPOSED TYPICAL CROSS SECTIONS
7	DETAILS & NOTES
8-10	MAINTENANCE OF TRAFFIC PLAN
11-14	PAVING PLANS
15	TRAFFIC SIGNAL DETECTOR LOOP REPLACEMENT PLAN
16	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING (BD 08)
17	CURB AND GUTTER REMOVAL AND REPLACEMENT (BD 24)
18	BUTT JOINT AND HMA TAPER DETAILS (BD 32)
19	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC 10)
20	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC 13)
21	TRAFFIC CONTROL AND PROTECTIONS AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (TC 14)
22	DISTRICT ONE - DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING (TS 07)

# I.D.O.T. STANDARD DRAWINGS

STANDARD NO.	TITLE OR DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
424001-05	CURB RAMPS FOR SIDEWALKS
442201-03	CLASS C&D PATCHES
604001-03	FRAMES AND LIDS, TYPE 1
701501-05	URBAN LANE CLOSURE, 2-LANE, 2-WAY, UNDIVIDED
701606-06	URBAN LANE CLOSURE, MULTILANE, 2-WAY, WITH MOUNTABLE MEDIAN
701701-06	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-04	LANE CLOSURE, MULTILANE, 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS
886001-01	DETECTOR LOOP INSTALLATION
886006-01	TYPICAL LAYOUTS FOR DETECTION LOOPS

# LEGEND OF SYMBOLS

(TO BE USED IN CONJUNCTION WITH I.D.O.T. STANDARD 000001-05)

SYMBOL	DESCRIPTION
	EXISTING HOT-MIX ASPHALT AREA
	EXISTING CONCRETE AREA
	EXISTING GRASS AREA
	PROPOSED HOT-MIX ASPHALT BUTT JOINT
	EXISTING CONCRETE SIDEWALK OR DRIVEWAY REMOVAL
	PROPOSED CONCRETE AREA, 5" SIDEWALK, 7" DRIVEWAY, 8" DRIVEWAY
	PROPOSED HOT-MIX ASPHALT PAVING AREA
	PROPOSED CLASS D PATCHES
	PROPOSED DETECTABLE WARNINGS
<b>A</b>	STRUCTURE TO BE ADJUSTED
<b>A*</b>	STRUCTURE TO BE ADJUSTED (SPECIAL)
<b>1C</b>	NEW FRAME AND LID, TYPE 1, CLOSED LID
<b>1P</b>	NEW FRAME AND LID, TYPE 1, OPEN LID
<b>RC</b>	STRUCTURE TO BE RECONSTRUCTED
	EXISTING DOMESTIC WATER SERVICE BOX
	EXISTING FIRE HYDRANT
	EXISTING WATER VALVE BOX
	EXISTING WATER MAIN VALVE VAULT
	EXISTING STORM SEWER INLET
	EXISTING STORM SEWER CATCH BASIN
	EXISTING SEWER MANHOLE
	EXISTING STREET LIGHT POLE
	EXISTING POWER POLE
	EXISTING TRAFFIC SIGNAL POLE
	EXISTING TRAFFIC SIGNAL MAST ARM
	EXISTING HANDHOLE
	DOUBLE HANDHOLE
	EXISTING TRAFFIC SIGNAL OR STREET LIGHT CONTROLLER
	EXISTING TRAFFIC SIGNAL MANHOLE
	EXISTING CURB AND GUTTER
	PROPOSED COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT

Drawing file: W:\Projects\12509095 - Profile Ave LAPP\INDEX.dwg Aug 26, 2009 - 8:06am

**HANCOCK ENGINEERING**  
 Civil Engineers  
 Municipal Consultants  
 Established 1911

USER NAME	DESIGNED	WOP	REVISED
	DRAWN	LEV/MK	
	CHECKED	JG	
	DATE	8-17-09	

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, I.D.O.T. STANDARD  
DRAWINGS, AND LEGEND OF SYMBOLS**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2732	09-00124-00-RS	COOK	22	2

CONTRACT NO. 63296  
 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003 (302)