

CODE NUMBER	PAY ITEM	UNIT	TOTAL	GARFIELD STREET		FIRST STREET	PARK AVENUE
				PARTICIPATING (100% FEDERAL A.R.R.A. FUNDS)	NON-PARTICIPATING (100% VILLAGE OF HINSDALE FUNDS)	NON-PARTICIPATING (100% VILLAGE OF HINSDALE FUNDS)	NON-PARTICIPATING (100% VILLAGE OF HINSDALE FUNDS)
				I000	Y060-	Y060-	Y060-
20101000	TEMPORARY FENCE	FOOT	214			214	
20101100	TREE TRUNK PROTECTION	EACH	36	25		3	8
20101200	TREE ROOT PRUNING	EACH	26	20		2	4
20200100	EARTH EXCAVATION	CU YD	117	117			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	320	320			
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	53	53			
20800150	TRENCH BACKFILL	CU YD	4,411	2,392	1,001	384	634
20900110	POROUS GRANULAR BACKFILL	CU YD	267	267			
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	50	30		10	10
25200110	SODDING, SALT TOLERANT	SQ YD	2,038	1,297		393	348
28000400	PERIMETER EROSION BARRIER	FOOT	805	805			
28000500	INLET AND PIPE PROTECTION	EACH	37	37			
35101600	AGGEGATE BASE COURSE, TYPE B 4"	SQ YD	5,011	3,763		580	668
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,383	2,982		203	198
40600300	AGGREGATE (PRIME COAT)	TON	68	60		4	4
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	24	20		2	2
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL • BUTT JOINT	SQ YD	1,436	949		277	210
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2,190	2,190			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,764	1,315		227	222
42300710	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH, SPECIAL	SQ YD	196	149		35	12
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	17,799	17,319		225	255
42400800	DETECTABLE WARNINGS	SQ FT	604	460		64	80
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	4,005			2,023	1,982
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	14,912	14,912			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	112	112			
44000600	SIDEWALK REMOVAL	SQ FT	12,882	12,402		225	255
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	7,592	7,350		134	108
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	4,925	3,698		580	647
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	65	65			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2,000			900	1,100
45100200	CRACK FILLING	POUND	618			309	309
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	28	28			
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	40	40			
550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	250	250			
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	424	424			
550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	508	508			
550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	306	306			
550A2550	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 21"	FOOT	290	290			

• SPECIALTY ITEM • SEE SPECIAL PROVISIONS, PLAN DETAILS, OR PLAN NOTE FOR CLARIFICATION.



USER NAME = sjohnson
 PLOT SCALE = NONE
 PLOT DATE = 8/20/2009

DESIGNED -
 DRAWN - SVJ
 CHECKED - GT
 DATE - 8/20/09

REVISED -
 REVISED -
 REVISED -
 REVISED -

VILLAGE OF HINSDALE
 DUPAGE COUNTY, ILLINOIS
 GARFIELD STREET, FIRST STREET, & PARK AVENUE

SUMMARY OF QUANTITIES
 SCALE: NONE SHEET NO. 3 OF 65 SHEETS STA. TO STA.

F.A.U. RTE. 2678 SECTION NO. 08-00086-00-RS COUNTY DUPAGE TOTAL SHEETS 65 SHEET NO. 3 CONTRACT NO. 63297
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

PROJECT CONTACT: G. THOMPSON, P.E. SEC. PROJ. NO. 080086-RS-00086-00-RS-0001-001 8/20/09