

CODE NUMBER	PAY ITEM	UNIT	TOTAL	GARFIELD STREET		FIRST STREET	PARK AVENUE
				PARTICIPATING (100% FEDERAL A.R.R.A. FUNDS)	NON-PARTICIPATING (100% VILLAGE OF HINSDALE FUNDS)	NON-PARTICIPATING (100% VILLAGE OF HINSDALE FUNDS)	NON-PARTICIPATING (100% VILLAGE OF HINSDALE FUNDS)
				1000	Y060-	Y060-	Y060-
⊗ X0323842	WATER MAIN LINE STOP 12"	EACH	3			2	1
• X0324864	DRAIN CONNECTIONS	FOOT	250	250			
⊗ • X0351580	PVC WATER MAIN 12"	FOOT	1,393			696	697
• X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	72	62			10
• X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	18	14		3	1
• X4023000	TEMPORARY ACCESS (ROAD)	EACH	11	9		1	1
X7030104	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 4 INCH	FOOT	558	558			
X7030106	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 6 INCH	FOOT	226	226			
X7030112	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 12 INCH	FOOT	80	80			
X7030120	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, LETTERS AND SYMBOL	SQ FT	98.8	98.8			
XX000406	BRICK PAVER REMOVAL AND REPLACEMENT	SQ FT	128	128			
⊗ XX001987	LINE STOPS 4"	EACH	1				1
XX002905	CONFLICT MANHOLE, 6' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
⊗ • XX002907	WATER SERVICE CONNECTION (SHORT)	EACH	19		11	3	5
⊗ • XX003213	ADJUSTING WATER SERVICE LINES	EACH	25		16	6	3
⊗ • XX003516	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 8"	EACH	3		1	1	1
⊗ • XX003517	CONNECTIONS TO EXISTING WATER MAINS (NON PRESSURE) - 6"	EACH	5		5		
⊗ • XX003518	CONNECTIONS TO EXISTING WATER MAINS (NON PRESSURE) - 4"	EACH	1		1		
• XX003822	STORM SEWER REMOVAL, SPECIAL	FOOT	160	160			
⊗ • XX004689	SANITARY SERVICE TO BE ADJUSTED	EACH	20		20		
• XX004812	VIDEO TAPING OF SEWERS	FOOT	5,374	2,710	2,664		
⊗ • XX004999	PVC WATER MAIN 8"	FOOT	1,786		1,743	22	21
⊗ • XX005107	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 12"	EACH	2			1	1
⊗ • XX005541	CURED-IN-PLACE PIPE (CIPP), 12"	FOOT	103		103		
⊗ • XX005542	CURED-IN-PLACE PIPE (CIPP), 15"	FOOT	213		213		
⊗ • XX005554	CURED-IN-PLACE PIPE (CIPP), 24"	FOOT	2,248		2,248		
⊗ • XX006247	SANITARY SEWER REMOVAL	FOOT	75		75		
⊗ • XX006814	WATER SERVICE CONNECTION (LONG)	EACH	23		9	6	8
• XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	161	161			
• XX007357	CLASS C PATCHES (SPECIAL)	SQ YD	21				21
• Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	4	4			
⊗ • Z0045100	PRESSURE CONNECTION 12"x12"	EACH	1				1
△ Z0076600	TRAINEES	hour	500	500			
⊗ • XX008185	PVC WATERMAIN, 4"	FOOT	22				22
• XX008186	SALVAGING EXISTING BRICK PAVERS	EACH	713	553		80	80
⊗ • XX008187	SANITARY SEWER MANHOLE INTERIOR REHABILITATION	FOOT	165		165		
⊗ • XX008188	SANITARY SEWER REPAIR, REMOVE AND REPLACE	FOOT	45		45		

• SEE SPECIAL PROVISIONS, PLAN DETAILS, OR PLAN NOTE FOR CLARIFICATION.
⊗ SPECIALTY ITEM
△ 4080



USER NAME = s.johnson	DESIGNED -	REVISED -
PLOT SCALE = NONE	DRAWN - SVJ	REVISED -
PLOT DATE = 8/20/2009	CHECKED - GT	REVISED -
	DATE = 8/20/09	REVISED -

**VILLAGE OF HINSDALE
DUPAGE COUNTY, ILLINOIS
GARFIELD STREET, FIRST STREET, & PARK AVENUE**

SUMMARY OF QUANTITIES	
SCALE: NONE	SHEET NO. 5 OF 65 SHEETS
STA.	TO STA.

F.A.U. RTE. 2678	SECTION NO. 08-00086-00-RS	COUNTY DUPAGE	TOTAL SHEETS 65	SHEET NO. 5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63297	