

PAVEMENT QUANTITIES SCHEDULE											
STA	ADDRESS/LOCATION	PAVEMENT WIDTH (FT)	PAVEMENT LENGTH (FT)	PAVEMENT AREA (SQ FT)	PAVEMENT AREA (SQ YD)	LEVEL BIND (MM, N70)	40600635 HMA SURF. (TONS)	40600340 CSE, MIX D, N70 (GALLON)	40600100 BIT MATL. PR. COAT (TONS)	40600300 AGGREGATE PR. COAT (TONS)	44000161 HMA SURFACE REMOVAL, 3" (SQ YD)
34+41 to 51+00	MAINLINE	54.7	1,659	90,747	10,083.0	564.6	1,129.3	2,016.6	40.3	10,083.0	
51+00 to 65+70	MAINLINE	60	1,470	88,200	9,800.0	548.8	1,097.6	1,960.0	39.2	9,800.0	
49+75	BARBARA LANE INTERSECTION	55	35	1,925	213.9	12.0	24.0	42.8	0.9	213.9	
51+80	DRIVEWAY	55	29	1,595	177.2	9.9	19.8	35.4	0.7	177.2	
55+60	SEASONS RIDGE INTER. - LT	55	40	2,200	244.4	13.7	27.4	48.9	1.0	244.4	
55+60	SEASONS RIDGE INTER. - RT	60	50	3,000	333.3	18.7	37.3	66.7	1.3	333.3	
61+70	DRIVEWAY	50	22	1,100	122.2	6.8	13.7	24.4	0.5	122.2	
						<b>1174.6</b>	<b>2349.1</b>	<b>4194.8</b>	<b>83.9</b>	<b>20974.1</b>	
						TONS	TONS	GALLON	TONS	SY	

SIDEWALK REMOVAL AND REPLACEMENT SCHEDULE										
STA	DIRECTION	ADDRESS/LOCATION	SW REM. & REPL. (SPL) WIDTH (FT)	SW REM. & REPL. (SPL) LENGTH (FT)	44004610 SW REM. & REPL. (SPL) (SQ FT)	DETECTABLE WARNINGS WIDTH (FT)	DETECTABLE WARNINGS LENGTH (FT)	42400800 DETECTABLE WARNINGS (SQ FT)		
34+70	RT	BURGER KING	4.1	9	36.9	4	2	8.0		
34+80	RT	BURGER KING	5	2.2	11.0					
36+00	RT	BURGER KING	4.1	5.6	23.0					
35+50	RT	BURGER KING	4	6	24.0	3	2	6.0		
37+00	RT	EMPTY LOT	4	5	20.0	3	2	6.0		
39+60	RT	EMPTY LOT	4	6.5	26.0	3	2	6.0		
40+00	RT	EMPTY LOT	5	5	25.0	4	2	8.0		
40+30	RT	EMPTY LOT	5	9	45.0					
41+50	RT	EMPTY LOT	5	8	40.0	4	2	8.0		
41+80	RT	GOLDEN BUFFET	5	7.5	37.5	4	2	8.0		
43+70	RT	GOLDEN BUFFET	5	16.5	82.5			0.0		
44+10	RT	GOLDEN BUFFET	5	6.5	32.5	4	2	8.0		
44+70	RT	MARKET PLACE	5	7	35.0	4	2	8.0		
46+50	RT	MARKET PLACE	5	5	25.0					
47+50	RT	MARKET PLACE	5	4	20.0	4	2	8.0		
48+00	RT	MARKET PLACE	5	6	30.0	4	2	8.0		
49+40	RT	MARKET PLACE	4.6	7.2	33.1	4	2	8.0		
50+00	RT	DUNKIN DONUTS	6	4	24.0	4	2	8.0		
51+00	RT	DUNKIN DONUTS	5	5	25.0					
51+50	RT	DUNKIN DONUTS	5	24	120.0	4	2	8.0		
52+10	RT	KFC	5	3	15.0	4	2	8.0		
53+20	RT	KFC	5	10	50.0	4	2	8.0		
53+35	RT	KFC	5.5	7	38.5	4	2	8.0		
53+50	RT	WALGREENS	6.5	6.5	42.3	4	2	8.0		
53+65	RT	WALGREENS	5.5	5.5	30.3	4	2	8.0		
55+20	RT	WALGREENS	5	13	65.0					
55+25	RT	WALGREENS	5.5	8	44.0	4	2	8.0		
56+00	RT	DAIRY QUEEN	7	9	63.0	4	2	8.0		
57+00	RT	DAIRY QUEEN	5	160	800.0			0.0		
57+70	RT	DAIRY QUEEN	5	7.5	37.5	4	2	8.0		
58+30	RT	KENDALL MEDICAL CARE	5	6	30.0	4	2	8.0		
60+00	RT	KENDALL MEDICAL CARE	5	5	25.0					
60+50	RT	KENDALL MEDICAL CARE	5	5	25.0					
61+40	RT	KENDALL MEDICAL CARE	5	5	25.0	4	2	8.0		
62+00	RT	FIRST FINANCIAL BANK	5	3.5	17.5	4	2	8.0		
63+70	RT	FIRST FINANCIAL BANK	5	6	30.0	4	2	8.0		
64+30	RT	MOBIL	5	6	30.0	4	2	8.0		
64+80	RT	MOBIL	5	5	25.0	4	2	8.0		
65+40	RT	MOBILE	5	8	40.0	4	2	8.0		
56+00	LT	WEST SUBURBAN BANK	6	4.5	27.0	4	2	8.0		
55+20	LT	GRANDMA'S TABLE	6	3	18.0	4	2	8.0		
54+50	LT	GRANDMA'S TABLE	6	7.5	45.0	4	2	8.0		
53+50	LT	AUTO ZONE	5	20	100.0					
49+30	LT	THRIFT SHOP	5.5	20	110.0	4	2	8.0		
48+10	LT	THRIFT SHOP	5.5	8	44.0	4	2	8.0		
47+40	LT	BLOCKBUSTER	6	8.5	51.0	4	2	8.0		
46+00	LT	BLOCKBUSTER	5.5	11.5	63.3	4	2	8.0		
45+50	LT	ALDI	6	8	48.0	4	2	8.0		
44+70	LT	ALDI	5	6.5	32.5	4	2	8.0		
44+10	LT	MERLINS	5	7	35.0	4	2	8.0		
43+00	LT	MERLINS	5	25	125.0					
42+50	LT	MERLINS	5	7.5	37.5	4	2	8.0		
					565.0	2884.7		314.0		
					SF	SF		SF		

BUTT JOINT AND TEMPORARY RAMP SCHEDULE						
STA	SIDE	LENGTH (FT)	WIDTH (FT)	40600982 HMA SURF. REM. BUTT JOINT (SQ YD)	SIDE ROAD BUTT JOINT LOCATION - AS MEASURED FROM MAINLINE (FT)	40600990 TEMPORARY RAMP (SQ YD)
34+41	BUTT	65	4.5	33		
36+70	RT	54	2			12
39+85	RT	45	2			10
41+70	RT	70	2			16
42+15	LT	60	2			14
44+50	RT	80	2			18
44+50	LT	80	2			18
45+85	LT	60	2			14
47+75	LT	80	2			18
48+75	RT	80	2			18
49+75	RT	80	2			18
49+75	LT/BUTT	40	4.5	20	35	
51+75	RT/BUTT	40	4.5	20	29	
51+75	LT	60	2			14
53+30	RT	60	2			14
54+40	LT	50	2			12
55+65	RT/BUTT	45	4.5	23	40	
55+65	LT/BUTT	60	4.5	30	50	
58+10	RT	70	2			16
61+65	RT	80	2			18
61+65	LT/BUTT	60	4.5	30	22	
64+00	RT	60	2			14
65+10	RT	40	2			9
65+70	BUTT	65	4.5	33		
				189.0		253.0
				SY		SY

DRIVEWAY TEMPORARY RAMPS SHALL BE 2' WIDE

PATCHING SCHEDULE				
STA	PAVEMENT PATCH WIDTH (FT)	PAVEMENT PATCH LENGTH (FT)	REPAIR AREA (SQ FT)	44201771 REPAIR AREA - TY IV (SQ YD)
42+00	12	50	600	67.0
43+10	7	35	245	28.0
45+50	12	30	360	40.0
47+00	12	50	600	67.0
49+75	2	110	220	25.0
49+75	7	50	350	39.0
52+50	7	35	245	28.0
55+50	12	50	600	67.0
55+50	12	50	600	67.0
64+00	7	55	385	43.0
				471.0
				SY

ADJUSTMENT SCHEDULE				
STA	OFFSET	X0321556 SANITARY M.H. TO BE ADJ. (EACH)	60255500 MANHOLES TO BE ADJ. (EACH)	81400115 HANDHOLE TO BE ADJ. (EACH)
34+75	5' RT		1	
36+85	17' RT	1		
39+85	11' RT	1		
55+02	6' RT			1
56+24	6' RT			1
65+65	0' RT			1
		2	1	3
		EACH	EACH	EACH

CURB AND GUTTER REMOVAL AND REPLACEMENT SCHEDULE						
STA	DIRECTION	ADDRESS/LOCATION	44001700 CURB & GUTTER REM. & REPL. LENGTH (FT)	44002400 CURB REMOVAL (SPECIAL) LENGTH (FT)	XX006947 HMA DRIVEWAY REM. & REPLACE. AREA (SQ YD)	
39+00	RT	EMPTY LOT	80.0			
42+00	RT	GOLDEN BUFFET	65.0			
46+60	RT	MARKET PLACE	20.0			
48+00	RT	MARKET PLACE	50.0		12.0	
51+50	RT	DUNKIN DONUTS	30.0			
52+00	RT	KFC	20.0			
53+70	RT	WALGREENS	20.0			
54+60	RT	WALGREENS	30.0			
57+00	RT	DAIRY QUEEN	135.0			
58+30	RT	KENDALL MEDICAL CARE	35.0			
61+10	RT	KENDALL MEDICAL CARE	20.0			
63+00	RT	FIRST FINANCIAL BANK	100.0			
64+50	RT	MOBIL	30.0			
63+00	LT	TACO BELL	100.0			
60+00	LT	PIZZA HUT	30.0			
57+00	LT	PIZZA HUT	100.0			
55+40	LT	GRANDMA'S TABLE	35.0			
54+50	LT	GRANDMA'S TABLE	7.0			
53+00	LT	AUTO ZONE	40.0			
50+00	LT	BARBARA LANE	10.0			
49+75	LT	BARBARA LANE		110.0		
47+00	LT	BLOCKBUSTER	60.0			
45+50	LT	ALDI	35.0			
45+20	LT	ALDI	15.0			
44+70	LT	ALDI	10.0			
44+30	LT	MERLINS	30.0		7.0	
44+20	LT	MERLINS	10.0			
43+00	LT	MERLINS	63.0			
39+50	LT	CEMETERY	110.0			
36+00	LT	CEMETERY	200.0			
			1510.0	110.0	19.0	
			FT	FT	SQ YD	

STRIP REFLECTIVE CRACK CONTROL TREATMENT SCHEDULE			
STA	OFFSET	44300200 STRIP REFLC. CRACK CONTROL TREAT. (FOOT)	
40+23 to 53+23	13' RT	1300	
40+23 to 53+23	13' LT	1300	
TRANSVERSE CRACKING (AS NEEDED)		540	
		3140	
		FOOT	

RESTORATION SCHEDULE				
STA/LOCATION	RESTORATION WIDTH (FT)	RESTORATION LENGTH (FT)	RESTORATION AREA (SQ FT)	XX006425 RESTORATION AREA (SQ YD)
BEHIND CURB AND GUTTER REMOVAL	2	1510	3020	335.6
ADJACENT TO SIDEWALK REMOVAL	2	565	1130	125.6
STA 37+00 - FILL IN LOW SPOT BEHIND CURB	4	8	32	3.6
STA 60+00 - FILL IN DEPRESSION	5	6	30	3.3
				468.0
				SY

NOTE:  
 ALL QUANTITIES SHOWN IN THE SCHEDULES ARE APPROXIMATE. THE ENGINEER WILL LOCATE ALL IMPROVEMENTS IN THE FIELD PRIOR TO CONSTRUCTION. PAYMENT SHALL BE BASED ON ACTUAL FIELD MEASUREMENTS.

Plotted: August 14, 2009 @ 10:21 AM By: Kris Pung - Tab: 08\_Schedule 22x34  
 COPYRIGHT © 2009 ENGINEERING ENTERPRISES, INC.