

SUMMARY OF QUANTITIES

| CODE NO.     | PAY ITEM   | UNIT   | CONST. CODE    |
|--------------|--|--------|----------------|
|              |  |        | 1000           |
|              |  |        | TOTAL QUANTITY |
| 40600100     | BITUMINOUS MATERIALS (PRIME COAT)                            | GALLON | 7,630          |
| 40600300     | AGGREGATE (PRIME COAT)                                       | TON    | 80             |
| 40600400     | MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS                    | TON    | 50             |
| 40600635     | LEVELING BINDER (MACHINE METHOD), N70                        | TON    | 2,140          |
| 40600895     | CONSTRUCTING TEST STRIP                                      | EACH   | 1              |
| Δ 40600982   | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT                 | SQ YD  | 220            |
| 40603340     | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70                 | TON    | 4,280          |
| Δ 42400800   | DETECTABLE WARNINGS  | SQ FT  | 176            |
| 44000157     | HOT-MIX ASPHALT SURFACE REMOVAL, 2"                          | SQ YD  | 22,020         |
| Δ 44000198   | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH              | SQ YD  | 16,120         |
| Δ 44001700   | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT   | 570            |
| Δ 44004610   | SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)                   | SQ FT  | 2,525          |
| Δ 44201803   | CLASS D PATCHES, TYPE II, 13 INCH                            | SQ YD  | 35             |
| Δ 44201807   | CLASS D PATCHES, TYPE III, 13 INCH                           | SQ YD  | 50             |
| Δ 44201809   | CLASS D PATCHES, TYPE IV, 13 INCH                            | SQ YD  | 260            |
| 44300100     | AREA REFLECTIVE CRACK CONTROL TREATMENT                      | SQ YD  | 38,140         |
| 60255500     | MANHOLES TO BE ADJUSTED                                      | EACH   | 9              |
| 60265700     | VALVE VAULTS TO BE ADJUSTED                                  | EACH   | 16             |
| 67100100     | MOBILIZATION   | L SUM  | 1              |
| Δ 70101700   | TRAFFIC CONTROL AND PROTECTION                               | L SUM  | 1              |
| 70106800     | CHANGEABLE MESSAGE SIGN                                      | CAL MO | 2              |
| 70300100     | SHORT-TERM PAVEMENT MARKING                                  | FOOT   | 3,630          |
| 70300220     | TEMPORARY PAVEMENT MARKING - LINE 4"                         | FOOT   | 25,230         |
| 70301000     | WORK ZONE PAVEMENT MARKING REMOVAL                           | SQ FT  | 1,210          |
| * 78000100   | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS         | SQ FT  | 500            |
| * 78000200   | THERMOPLASTIC PAVEMENT MARKING - LINE 4"                     | FOOT   | 23,500         |
| * 78000400   | THERMOPLASTIC PAVEMENT MARKING - LINE 6"                     | FOOT   | 1,730          |
| * 78000600   | THERMOPLASTIC PAVEMENT MARKING - LINE 12"                    | FOOT   | 505            |
| * 78000650   | THERMOPLASTIC PAVEMENT MARKING - LINE 24"                    | FOOT   | 365            |
| * 78100100   | RAISED REFLECTIVE PAVEMENT MARKER                            | EACH   | 410            |
| Δ * 81400115 | HANDHOLE TO BE ADJUSTED                                      | EACH   | 5              |
| Δ * 88600600 | DETECTOR LOOP REPLACEMENT                                    | FOOT   | 1,540          |
| Δ X0321556   | SANITARY MANHOLES TO BE ADJUSTED                             | EACH   | 8              |
| Δ XX003435   | PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT    | SQ YD  | 7              |
| Δ XX006425   | RESTORATION  | SQ YD  | 170            |
| Z0048665     | RAILROAD PROTECTIVE LIABILITY INSURANCE                      | L SUM  | 1              |

Δ SEE SPECIAL PROVISIONS  
\* SPECIALTY ITEMS

Printed: August 14, 2009 @ 10:57 AM By: Kris Pung - Tab: 03 Quantities - 22&34

Path: \\SISKIYOU\EG0901\DWG\DWG\_FINAL\ENG\EG0901-CVR

**Engineering Enterprises, Inc.**  
CONSULTING ENGINEERS  
52 Wheeler Road  
Sugar Grove, Illinois 60554  
630.466.6700 / www.eeiweb.com

**CITY OF ELGIN**

| NO. | DATE | REVISIONS |
|-----|------|-----------|
|     |      |           |
|     |      |           |
|     |      |           |

**BIG TIMBER ROAD  
LAPP IMPROVEMENTS**

**SUMMARY OF QUANTITIES**