

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURES	STRUCTURES
				I000	X220-2A	X271-2A
				100% FEDERAL		
20200100	EARTH EXCAVATION	CU YD	2785	2785		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	436		116	320
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3156	3156		
* 25000210	SEEDING, CLASS 2A	ACRE	0.50	0.50		
* 25000310	SEEDING, CLASS 4	ACRE	0.25	0.25		
: 25000750	MOWING	ACRE	0.75	0.75		
* 25100115	MULCH, METHOD 2	ACRE	0.75	0.75		
* 25100900	TURF REINFORCEMENT MAT	SQ YD	342	342		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	216	216		
28000300	TEMPORARY DITCH CHECKS	EACH	8	8		
28000400	PERIMETER EROSION BARRIER	FOOT	373	373		
28000500	INLET AND PIPE PROTECTION	EACH	2	2		
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	3156	3156		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	92	92		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	489	489		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	530	530		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	447	447		
44000100	PAVEMENT REMOVAL	SQ YD	2322	2322		
44004000	PAVED DITCH REMOVAL	FOOT	371	371		
44000700	APPROACH SLAB REMOVAL	SQ YD	853	853		
44200089	PAVEMENT PATCHING, TYPE I, 8 INCH	SQ YD	324	324		
44200094	PAVEMENT PATCHING, TYPE II, 8 INCH	SQ YD	324	324		
44200549	CLASS A PATCHES, TYPE I, 10 INCH	SQ YD	389	389		
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	389	389		
44213000	PATCHING REINFORCEMENT	SQ YD	778	778		
44213200	SAW CUTS	FOOT	3684	3684		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2		2	
50102400	CONCRETE REMOVAL	CU YD	78			78
50104650	SLOPE WALL REMOVAL	SQ YD	2185		980	1205
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	2			2
50157300	PROTECTIVE SHIELD	SQ YD	926		456	470

* SPECIALTY ITEM
: NON-PARTICIPATION (100% STATE)

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
at:\pw\work\pwidot\cushmanbw\dms36777\0200298-shr-cover.dgn		DRAWN -	REVISED -			74	37-(4HB,4HB-1,4HB-2)D	HENRY	148	2	
PLOT SCALE = 50.0000' / 1" IN.		CHECKED -	REVISED -			CONTRACT NO. 64264					
PLOT DATE = Thu Aug 06 09:31:48 2009		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.