

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURES	STRUCTURES
				I000	X220-2A	X271-2A
50200100	STRUCTURE EXCAVATION	CU YD	546		170	376
50300100	FLOOR DRAINS	EACH	24			24
50300225	CONCRETE STRUCTURES	CU YD	289.3		106.5	182.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1578.2		915.8	662.4
50300260	BRIDGE DECK GROOVING	SQ YD	3171		1429	1742
50300280	CONCRETE ENCASEMENT	CU YD	8.4		8.4	
50300300	PROTECTIVE COAT	SQ YD	3863		1746	2117
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	15,980		6,060	9,920
50500505	STUD SHEAR CONNECTORS	EACH	6134			6134
20031200	JACKING AND CRIBBING	EACH	28			28
50600300	CLEANING AND PAINTING STEEL BRIDGE	L SUM	1			1
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1			1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	377,700		209,390	168,310
50800515	BAR SPLICERS	EACH	2359		870	1489
51100100	SLOPE WALL 4 INCH	SQ YD	2013		800	1213
51201400	FURNISHING STEEL PILES HP10X42	FOOT	1200		1200	
51202305	DRIVING PILES	FOOT	1200		1200	
51205200	TEMPORARY SHEET PILING	SQ FT	1487		518	969
51500100	NAME PLATES	EACH	4		2	2
52000110	PREFORMED JOINT STRIP SEAL	FOOT	176.5			176.5
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	46		18	28
52100520	ANCHOR BOLTS, 1"	EACH	128		72	56
542D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	108	108		
54213447	END SECTIONS 12"	EACH	4	4		
54215763	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	4	4		
58700300	CONCRETE SEALER	SQ FT	814			814
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	213		68	145
60108000	PIPE UNDERDRAINS 12"	FOOT	115	115		
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	591		263	328
60900115	TYPE B INLET BOX, STANDARD 609001	EACH	2	2		

* SPECIALTY ITEM

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pwork\pwork\cushmanbw\dms36777\020298-shft-cover.dgn		DRAWN -	REVISED -			74	37-(4HB,4HB-1,4HB-2)D	HENRY	148	3
PLOT SCALE = 50.0000 / IN.		CHECKED -	REVISED -							
PLOT DATE = Thu Aug 06 09:32:00 2009		DATE -	REVISED -							
					SCALE:	SHEET NO. OF SHEETS		STA. TO STA.		
ILLINOIS FED. AID PROJECT										