



20200100	FARTH EXCAVATION		28000300	TEMPORARY DITCH CHECKS		40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING
	CU YD LOCATION REMARKS		EACH LOCATION REMARKS			TON LOCATION REMARKS	
	155 LT Sta. 1347+58 to 1349+93		1 RT Sta. 1349+15			10 LT PE Sta. 1348+46.50	
	330 RT Sta. 1347+89 to 1350+01		1 RT Sta. 1349+55			10 TOTAL	
	1,320 LT Sta. 1350+57 to 1361+02		2 LT & RT Sta. 1351+00				
	11,695 Rt Sta. 1350+75 to 1361+02		1 RT Sta. 1352+00				
	13,500 TOTAL		1 LT Sta. 1352+70				
			1 RT Sta. 1354+30				
21301084	EXPLORATION TRENCH 84" DEPTH		1 RT Sta. 1355+00			44004250	PAVED SHOULDER REMOVAL
	FOOT LOCATION REMARKS		1 LT Sta. 1356+25			SQ YD LOCATION REMARKS	
	50 RT Sta. 1350+15		1 RT Sta. 1358+00			41 LT Sta. 1348+46.50 PE	
	50 RT Sta. 1350+70		1 RT Sta. 1358+30			29 RT Sta. 1348+50 MBTO	
	50 RT Sta. 1359+05		1 LT Sta. 1360+00			51 RT Sta. 1350+00 to 1350+65	Stage II
	150 TOTAL		12 TOTAL			121 TOTAL	
25000210	SEEDING, CLASS 2A		28000400	PERIMETER EROSION BARRIER		44201433	CLASS C PATCHES, TYPE IV, 16"
	ACRE LOCATION REMARKS		FOOT LOCATION REMARKS			SQ YD LOCATION REMARKS	
	0.15 LT Sta. 1347+58 to 1349+93		210 LT Sta. 1347+65 to 1349+90			191 Sta. 1349+97 to 1350+62	
	0.15 RT Sta. 1347+89 to 1350+01		210 TOTAL			191 TOTAL	
	0.6 LT Sta. 1350+57 to 1361+02						
	1.1 Rt Sta. 1350+75 to 1361+02						
	2.0 TOTAL						
25000310	SEEDING, CLASS 4		28000500	INLET AND PIPE PROTECTION		48101200	AGGREGATE SHOULDERS, TYPE B
	ACRE LOCATION REMARKS		EACH LOCATION REMARKS			TON LOCATION REMARKS	
	0.35 LT Sta. 1350+57 to 1361+02		1 RT Sta. 1348+17.62			13.4 LT Sta. 1347+59 to 1348+18	
	2.4 Rt Sta. 1350+75 to 1361+02		1 TOTAL			2 LT Sta. 1348+46.50 PE	
	2.75 TOTAL					197 RT Sta. 1352+15 to 1361+00	
						201.6 LT Sta. 1352+35 to 1361+00	
						6 RT Sta. 1347+90 to 1348+12	
						420 TOTAL	
25000400	NITROGEN FERTILIZER NUTRIENT		28200200	FILTER FABRIC		48203029	HOT-MIX ASPHALT SHOULDERS, 8"
	POUND LOCATION REMARKS		SQ YD LOCATION REMARKS			SQ YD LOCATION REMARKS	
	14 LT Sta. 1347+58 to 1349+93		3,620 SN 037-2027			515 LT Sta. 1348+14 to 1352+37	
	14 RT Sta. 1347+89 to 1350+01		3,620 TOTAL			469 RT Sta. 1348+12 to 1352+15	
	87 LT Sta. 1350+57 to 1361+02					51 RT Sta. 1350+00 to 1350+65	Stage II
	315 Rt Sta. 1350+75 to 1361+02					1,035 TOTAL	
	430 TOTAL						
25000500	PHOSPHOROUS FERTILIZER NUTRIENT		31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"		50104400	CONCRETE HEADWALL REMOVAL
	POUND LOCATION REMARKS		SQ YD LOCATION REMARKS			EACH LOCATION REMARKS	
	14 LT Sta. 1347+58 to 1349+93		213 Sta. 1349+97 to 1350+62			2 RT FE Sta. 1348+17.62	
	14 RT Sta. 1347+89 to 1350+01		213 TOTAL			2 TOTAL	
	87 LT Sta. 1350+57 to 1361+02						
	315 Rt Sta. 1350+75 to 1361+02						
	430 TOTAL						
25000600	POTASSIUM FERTILIZER NUTRIENT		35101600	AGGREGATE BASE COURSE, TYPE B 4"		50105220	PIPE CULVERT REMOVAL
	POUND LOCATION REMARKS		TON LOCATION REMARKS			FOOT LOCATION REMARKS	
	14 LT Sta. 1347+58 to 1349+93		52 RT FE Sta. 1348+17.62			17 RT FE Sta. 1348+17.62	
	14 RT Sta. 1347+89 to 1350+01		10 LT PE Sta. 1348+46.50			17 TOTAL	
	87 LT Sta. 1350+57 to 1361+02		62 TOTAL				
	315 Rt Sta. 1350+75 to 1361+02						
	430 TOTAL						
25000750	MOWING		40201000	AGGREGATE FOR TEMPORARY ACCESS		54213459	END SECTIONS 24"
	ACRE LOCATION REMARKS		TON LOCATION REMARKS			EACH LOCATION REMARKS	
	0.15 LT Sta. 1347+58 to 1349+93		50 LT Sta. 1347+59 to 1348+39			2 RT FE Sta. 1348+17.62	
	0.15 RT Sta. 1347+89 to 1350+01		50 TOTAL			2 TOTAL	
	0.95 LT Sta. 1350+57 to 1361+02						
	3.5 Rt Sta. 1350+75 to 1361+02						
	4.75 TOTAL						
25100115	MULCH, METHOD 2		40600625	LEVELING BINDER (MACHINE METHOD), N50		54202229	PIPE CULVERTS, CLASS D, TYPE 1 24"
	ACRE LOCATION REMARKS		TON LOCATION REMARKS			FOOT LOCATION REMARKS	
	0.2 LT Sta. 1347+58 to 1361+02		242 Sta. 1348+62 to 1360+50			10 RT Sta. 1350+15	
	1.6 RT Sta. 1347+89 to 1361+02		242 TOTAL			10 TOTAL	
	1.8 TOTAL						
25100630	EROSION CONTROL BLANKET		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT		60100935	PIPE DRAINS 10"
	SQ YD LOCATION REMARKS		SQ YD LOCATION REMARKS			FOOT LOCATION REMARKS	
	9,500 RT Sta. 1347+89 to 1361+02		86.5 Sta. 1348+12			10 RT Sta. 1350+70	
	4,700 LT Sta. 1350+57 to 1361+02		86.5 Sta. 1361+00			10 TOTAL	
	14,200 TOTAL		173 TOTAL				
28000250	TEMPORARY EROSION CONTROL SEEDING		40600990	TEMPORARY RAMP		60100955	PIPE DRAINS 15"
	POUND LOCATION REMARKS		SQ YD LOCATION REMARKS			FOOT LOCATION REMARKS	
	60 LT Sta. 1347+58 to 1349+93		23 Sta. 1348+12			10 RT Sta. 1359+05	
	60 RT Sta. 1347+89 to 1350+01		23 Sta. 1361+00			10 TOTAL	
	380 LT Sta. 1350+57 to 1361+02		46 TOTAL				
	1,400 Rt Sta. 1350+75 to 1361+02						
	1,900 TOTAL						
			40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50		61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.
			TON LOCATION REMARKS			EACH LOCATION REMARKS	
			316 Sta. 1348+12 to 1361+00			1 RT Sta. 1350+15	
			64 LT Sta. 1348+14 to 1352+37			1 RT Sta. 1350+70	
			60 RT Sta. 1348+12 to 1352+15			1 RT Sta. 1359+05	
			440 TOTAL			3 TOTAL	